

# SUMMARY OF QUANTITIES

100% STATE  
SFTY-2A

paycode	description	units	total quantity
40600990	TEMPORARY RAMP	SQ YD	54
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	60
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	534
50102400	CONCRETE REMOVAL	CU YD	18.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	18.9
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2990
50800515	BAR SPLICERS	EACH	38
52000110	PREFORMED JOINT STRIP SEAL	FOOT	170
63300455	REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
<del>67000400</del>	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1500
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3480
* 70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	48
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1220
70400100	TEMPORARY CONCRETE BARRIER	FOOT	687.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1375
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3240
78300100	PAVEMENT MARKING REMOVAL	SQ FT	500
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	9
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2

GENERAL NOTES & INDEX OF SHEETS  
 US 30 OVER ELKHORN CREEK  
 FAS 1197 (US 30)  
 SECTION (110BR-1)M-1  
 WHITESIDE COUNTY  
 STRUCTURE NUMBER 098-0033

\* SPECIALTY ITEM

FILE NAME =	USER NAME = lmkdj	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>Summary of Quantities</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
G:\BRV\CADD plans\Whiteside County\0980033.dgn	DRAWN - ---	REVISED - ---	1197			(110BR-1)M-1	Whiteside	13	2	
PLOT SCALE = 50.0000' / IN.	CHECKED - ---	REVISED - ---	CONTRACT NO. 64E91							
PLOT DATE = Wed Jan 28 09:00:17 2009	DATE - ---	REVISED - ---	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____										