

# GENERAL NOTES

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then, use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Cubic Meter (Cubic Yard) for MOBILIZATION.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of MOBILIZATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the MOBILIZATION

At bridge expansion joints, if temporary expansion joint bulkheads are attached to adjacent deck slabs or abutments for support, the Contractor shall cut the attachments as soon as the concrete has set to prevent joint damage due to horizontal contraction or expansion.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

The following Mixture Requirements are applicable for this project:

Mixture Uses(s):	Surface	Level Binder
PG:	PG 64-22	PG 64-22
Design Air Voids	4.0 @ N50	4.0 @ N50
Mixture Composition		
(Gradation Mixture)	IL 9.5 or 12.5	IL 9.5
Friction Aggregate	D	n/a
20 Year ESAL	2.8	2.8
Mix Unit Weight - 112 lbs/sy/in		

Bituminous and Aggregate prime coat shall be placed in accordance with Section 406 of the Standard Specifications. The cost of the prime coats shall be included in the contract unit price per ton for HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 of the type specified.

# INDEX OF SHEETS

1. Cover Sheet
2. Summary of Quantities
3. General Notes, Index of Sheets
4. Traffic Control Plan
5. Roadway Approach Plan
6. General Plan & Elevation
7. Deck Plan & Cross-Section
8. Joint Details
9. Joint Details
10. Preformed Joint Strip Seal
11. Bar Splicers
12. District Standard
13. District Standard

# STANDARDS

- 701006-03
- 701201-03
- 701301-03
- 701321-10
- 701901-01
- 704001-05
- 720011-01
- 728001-01
- 729001-01

GENERAL NOTES & INDEX OF SHEETS  
US 30 OVER ELKHORN CREEK  
FAS 1197 (US 30)  
SECTION (110BR-1)M-1  
WHITESIDE COUNTY  
STRUCTURE NUMBER 098-0033

FILE NAME =	USER NAME = linkdj	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>General Notes Index of Sheets</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D:\BR\CA00 plans\Whiteside County\0980033.dgn	DRAWN - ---	REVISED - ---	1197			(110BR-1)M-1	Whiteside	13	3	
PLOT SCALE = 58.0000' / IN.	CHECKED - ---	REVISED - ---	CONTRACT NO. 64E91							
PLOT DATE = Wed Jan 28 09:00:24 2009	DATE - ---	REVISED - ---	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT							
SCALE: _____ SHEET NO. ___ OF ___ SHEETS   STA. _____ TO STA. _____										