

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(118,119) RS-4	GRUNDY	28	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ESP

SUMMARY OF QUANTITIES				100% FED
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000 ROADWAY
20400800	FURNISHED EXCAVATION	CU YD	30	30
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	28191	28191
40600300	AGGREGATE (PRIME COAT)	TON	405	405
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	116	116
40600535	LEVELING BINDER (HAND METHOD), N70	TON	193	193
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	8495	8495
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	17912	17912
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3344	3344
40600990	TEMPORARY RAMP	SQ YD	127	127
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	663	663
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	200177	200177
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	8465	8465
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ. YD	48	48
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3992	3992
60255500	MANHOLE TO BE ADJUSTED	EACH	1	1
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	4	4
66700095	PERMANENT SURVEY MARKERS	EACH	43	43
67100100	MOBILIZATION	L SUM	1	1

ESP

SUMMARY OF QUANTITIES				100% FED
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000 ROADWAY
70100460	TRAFFIC CONTROL <sup>AND</sup> PROTECTION, STANDARD 701306	L SUM	1	1
70102620	TRAFFIC CONTROL <sup>AND</sup> PROTECTION, STANDARD 701501	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20658	20658
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	264	264
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	112715	112715
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13376	13376
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	727	727
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	296	296
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	109	109
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6818	6818
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	264	264
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10520	10520
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	727	727
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	296	296
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	109	109
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	102195	102195
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	13376	13376
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	792	792
* 78200300	PRISMATIC CURB REFLECTOR	EACH	8	8
* 78200405	GUARDRAIL MARKERS	EACH	76	76
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	792	792
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

\* SPECIALTY ITEM

PLOT DATE = Jan 31, 2009 - 04:15:08 PM  
 FILE NAME = c:\work\p1001\BRAD01PC\summary.dgn  
 USER NAME = brad01pc

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_