

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(118,119) RS-4	GRUNDY	28	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIDEROAD SCHEDULE									
MAINLINE STATION	SIDE	LOCATION	LENGTH FT	WIDTH FT	AREA SQ. YD	INCIDENTAL HMA SURF. TONS	FURNISHED EXCAVATION* TONS	BIT. MAT. PR. CT. GALLONS	HMA SURF CSE MIX D, N70 TONS
172+91.67	RT	SCULLY RD	15	15.0 - 82.0	80.83	10.18	2.00	10.51	
172+91.67	LT	SCULLY RD	30	20.0 - 125.0	241.67	30.45	2.00	31.42	
225+99.27	RT	STONEWALL RD	30	30.0 - 115.0	241.67	30.45	2.00	31.42	
225+99.27	LT	STONEWALL RD	30	20.0 - 112.0	220.0	27.72	2.00	28.60	
278+92.32	RT	GOODFARM RD	30	17.0 - 105.0	203.33	25.62	2.00	26.43	
278+92.32	LT	GOODFARM RD	30	20.0 - 118.0	230	28.98	2.00	29.90	
331+92.51	RT	BECKER RD	30	20.0 - 106.0	210.0	26.46	2.00	27.30	
331+92.51	LT	BECKER RD	30	20.0 - 110.0	216.67	27.30	2.00	28.17	
384+90.91	RT	GARDNER RD	94	45.0 - 165.0	1096.67		2.00	142.57	138.18
384+90.91	LT	GARDNER RD							
491+02.98	LT	PRAIRE RD	30	20.0 - 102.0	203.33	25.62	2.00	26.43	
530+83.95	RT	SUCKER RD	30	20.0 - 92.0	186.67	23.52	1.00	24.27	
530+83.95	LT	SUCKER RD	30	19.0 - 94.0	188.33	23.73	1.00	24.48	
593+57.56	LT	SOUTH ST	30	27.0 - 84.0	185	23.31	1.00	24.05	
597+06.39	RT	GRAND RIDGE RD	95	26.0 - 203.0	1208.61		1.00	157.12	152.28
597+06.39	LT	GRAND RIDGE RD	61	35.0 - 232.0	904.83		1.00	117.63	114.01
612+90.00	RT	JONQUIL LN	30	36.0 - 134.0	283.33	35.70	1.00	36.83	
612+90.00	LT	JONQUIL LN	30	31.0 - 97.0	213.33	26.88	1.00	27.73	
650+09.32	RT	REED RD	30	20.0 - 88.0	180.0	22.68	1.00	23.40	
703+01.13	RT	SPRING RD	30	28.0 - 117.0	235	29.61	1.00	30.55	
703+01.13	LT	SPRING RD	30	19.0 - 100.0	198.33	24.99	1.00	25.78	
TOTAL					6728	443	30	875	404

\*FURNISHED EXCAVATION TO BE PLACED AT ALL SIDEROAD RADII- ALL AREAS OF FURNISHED EXCAVATION TO BE SEEDED AND FERTILIZED- SEEDING NOT BE PAID FOR SEPERATELY BUT INCLUDED IN THE COST OF FURNISHED EXCAVATION

TEMPORARY RAMP				
STATION TO STATION	LENGTH	WIDTH	SQ. YD.	
169+40.00	170+00.00	4	24	11
464+84.00	465+44.00	4	24	11
466+81.00	467+41.00	4	24	11
525+86.29	526+46.29	4	24	11
528+27.71	528+87.71	4	24	11
581+18.50	581+90.50	4	24	11
583+40.00	583+71.00	4	24	11
611+04.00	611+64.00	4	24	11
704+98.00	705+62.00	4	24	11
706+02.00	706+66.00	4	24	11
744+65.00	745+25.00	4	24	11
GRAND RIDGE ROAD				
7+49.00	8+09.00	4	22	10
TOTAL				127

PLOT DATE : Feb 02, 2009 - 01:57:10 PM  
 FILE NAME : c:\new-work\p\p\DOT\BRABO\PC\081161818 SUMMARY.DGN  
 USER : brabop  
 USER NAME : brabop