

Item No.	Item	Unit	Total	1000 ROADWAY	Y031-IF TRAFFIC SIGNALS US 45/52	Y031-IF TRAFFIC SIGNALS EDGEMERE DRIVE	Y031-IF TRAFFIC SIGNALS FIRE DEPT.	Y031-IF TRAFFIC SIGNALS WASHINGTON/MOONEY	SFTY-1B SIDEWALK	SFTY-2A BRIDGE RAIL
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	428.3	428.3	--	--	--	--	--	--
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4'	FOOT	17111	17111	--	--	--	--	--	--
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6'	FOOT	4213	4213	--	--	--	--	--	--
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8'	FOOT	2015	2015	--	--	--	--	--	--
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12'	FOOT	835	835	--	--	--	--	--	--
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24'	FOOT	618	618	--	--	--	--	--	--
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	439	439	--	--	--	--	--	--
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	24	24	--	--	--	--	--	--
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	--	--	--	--	--	--
* 81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	1006	--	279	--	--	727	--	--
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1185	--	--	--	65	1120	--	--
* 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	186	--	--	--	122	64	--	--
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	32	--	--	--	--	32	--	--
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	10	--	--	--	--	10	--	--
* 81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	192	--	--	--	--	192	--	--
* 81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	194	--	--	--	78	116	--	--
* 81306500	REMOVE EXISTING JUNCTION BOX	EACH	6	--	--	--	--	6	--	--
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5	--	--	--	1	4	--	--
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1629	--	52	--	187	1390	--	--
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	--	--	1	1	--	--	--
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	--	--	--	--	1	--	--
* 86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	1	--	--	--	--	1	--	--
* 87200500	TETHER WIRE	FOOT	161	--	--	161	--	--	--	--
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	525	--	--	--	525	--	--	--
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4785	--	--	--	537	4248	--	--
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2776	--	105	--	--	2671	--	--
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	146	--	--	--	--	146	--	--
* 87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL NO. 14 5C	FOOT	91	--	--	91	--	--	--	--
* 87302255	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL NO. 14 7C	FOOT	363	--	--	363	--	--	--	--
* 87501200	TRAFFIC SIGNAL POST, 16 FT	EACH	3	--	--	--	1	2	--	--
* 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT	EACH	1	--	--	--	--	1	--	--
* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT	EACH	1	--	--	--	1	--	--	--
* 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT	EACH	1	--	--	--	--	1	--	--
* 87702630	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 40 FT. AND 44 FT.	EACH	1	--	--	--	--	1	--	--
* 87702690	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 44 FT. AND 42 FT.	EACH	1	--	--	--	--	1	--	--
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	9	--	--	--	3	6	--	--

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	KANKAKEE	109	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* FAU ROUTE 6176 (ARMOUR ROAD)				
** SECTION (79)W&RS & 140RS				

PLOT DATE: 12/06
 PLOT SCALE: 1" = 100'
 USER NAME: ARR

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

 SUMMARY OF QUANTITIES
 FAU ROUTE 6176 (ARMOUR ROAD)
 SEC (79)W&RS & 140RS
 KANKAKEE COUNTY

SCALE: VERT. DRAWN BY: KKP
 DATE HORIZ. CHECKED BY: JKC