

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	KANKAKEE	109	14
STA. _____ TO STA. _____		ILLINOIS FED. AID PROJECT		
* FAU ROUTE 6176 (ARMOUR ROAD) ** SECTION (79)W&RS & 140RS				

LOCATION	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	TEMPORARY SIDEWALK	SIDEWALK REMOVAL	DETECTABLE WARNINGS
	SQ FT	SQ FT	SQ FT	SQ FT
STA. 100+52.46 TO STA. 100+75.06, LT	167	167	167	--
STA. 101+57.29 TO STA. 105+45.00, RT.	1759	1377	1377	--
* BELLE AIRE AVE.	477	323	323	30
STA. 106+31.60 TO STA. 108+16.60, RT.	793	691	691	--
* LE VASSEUR AVE.	495	353	353	31
STA. 109+03.50 TO STA. 111+00.0, RT.	792	658	658	--
* ASHLEY AVE.	226	163	163	29
* EDGEEMERE DR.	158	175	175	23
STA. 111+91.70 TO STA. 114+01.10, RT.	965	747	747	--
* BELMONT AVE.	169	131	131	31
STA. 114+92.10 TO STA. 118+31.59, RT.	1512	1028	1028	--
* STADIUM DR.	222	230	230	44
STA. 119+68.00 TO STA. 124+32.40, RT.	2077	1570	1570	--
* COUNTRY CT.	366	292	292	31
STA. 125+28.40 TO STA. 127+77.20, RT.	956	764	764	--
* TOMAGENE DR.	82	56	56	30
STA. 128+49.07 TO STA. 137+15.78, RT.	3585	--	--	26
--	--	--	--	--
--	--	--	--	--
TOTAL	14801	8725	8725	275

* SIDEWALK REPLACEMENT NECESSARY FOR WIDENING

LOCATION	THERMOPLASTIC PAVEMENT MARKING LINE							THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS	RAISED REFLECTIVE PAVEMENT MARKERS
	4"	6"		8"	12"		24"		
	YELLOW FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT		
STA. 98+00 TO STA. 104+00	892	---	351	529	36	127	76	61.6	33
STA. 104+00 TO STA. 110+00	1,778	---	428	202	140	---	31	35.2	40
STA. 110+00 TO STA. 116+00	994	40	594	205	22	---	125	52.8	35
STA. 116+00 TO STA. 122+00	1,748	80	426	160	79	---	29	44.0	41
STA. 122+00 TO STA. 128+00	812	40	400	---	78	---	109	17.6	41
STA. 128+00 TO STA. 134+00	1,393	200	374	---	84	---	16	35.2	45
STA. 134+00 TO STA. 140+00	993	---	220	332	52	---	133	52.8	34
STA. 140+00 TO STA. 146+00	2,261	---	300	70	217	---	---	8.8	46
STA. 146+00 TO STA. 152+00	1,291	---	160	---	---	---	---	---	28
STA. 152+00 TO STA. 158+00	2,400	---	300	---	---	---	---	---	44
STA. 158+00 TO STA. 164+00	1,255	---	260	20	---	---	99	---	29
STA. 164+00 TO STA. 170+00	---	---	40	95	---	---	---	17.6	4
EDGEEMERE DR.	129	---	---	---	---	---	---	---	---
WASHINGTON AVE.	239	---	---	---	---	---	---	---	---
ERNEST MOONEY DR.	658	---	---	371	---	---	---	79.2	19
STADIUM DR.	207	---	---	---	---	---	---	---	---
ENTRANCE ROAD (RT. STA. 161+50)	61	---	---	31	---	---	---	23.5	---
---	---	---	---	---	---	---	---	---	---
---	---	---	---	---	---	---	---	---	---
TOTAL	17,111	4,213	2,015	835	---	618	---	428.3	439

† THE QUANTITIES FOR TEMPORARY PAVEMENT MARKING SHALL BE THE SAME AS THERMOPLASTIC PAVEMENT MARKING.

LOCATION	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	COMBINATION CURB AND GUTTER REMOVAL
	FOOT	FOOT	FOOT
STA. 103+48.00, RT TO STA. 106+00.00, RT	256		255
STA. 103+48.80, LT TO STA. 127+64.93, LT	2,724	108	3,425
STA. 106+00.00, RT TO STA. 108+50.00, RT	298		322
STA. 108+50.00, RT TO STA. 111+50.00, RT	312		312
STA. 111+50.00, RT TO STA. 114+50.00, RT	329		329
STA. 114+50.00, RT TO STA. 119+09.43, RT	556		656
STA. 119+09.43, RT TO STA. 124+75.00, RT	600		706
STA. 124+75.00, RT TO STA. 128+25.00, RT	369		406
STA. 127+64.93, LT TO STA. 136+59.11, LT	1,046		1,081
STA. 136+59.11, LT TO STA. 147+53.63, LT	1,201		1,152
STA. 128+25.00, RT TO STA. 137+81.79, RT	917		931
STA. 137+81.79, RT TO STA. 147+45.45, RT	935		934
STA. 153+05.00, LT TO STA. 153+55.00, LT	50		50
TOTAL	9,593	108	10,559

LOCATION (STA. TO STA.)	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL			TERMINAL MARKER DIRECT APPLIED	GUARDRAIL REFLECTORS
		TYPE 2	TYPE 6A	TYPE 1 SPECIAL (TANGENT)		
	FOOT	EACH	EACH	EACH	EACH	EACH
STA. 141+53.76 TO STA. 147+41.13, LT.	587.5	1	1	---	1	6
STA. 141+57.42 TO STA. 147+32.39, RT.	575	---	1	1	---	6
STA. 149+83.61 TO STA. 152+71.11, LT.	287.5	---	1	1	---	6
STA. 149+74.87 TO STA. 155+12.08, RT.	537.5	1	1	---	1	6
TOTAL	1987.5	2	4	2	2	24

LOCATION (STA. TO STA.)	GUARDRAIL REMOVAL
	FOOT
STA. 141+25.07 TO STA. 147+62.11, LT	637
STA. 141+53.03 TO STA. 147+46.12, RT	593
STA. 149+62.78 TO STA. 152+75.29, LT	313
STA. 149+53.58 TO STA. 155+42.72, RT	589
TOTAL	2,132

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
FAU ROUTE 6176 (ARMOUR ROAD)
SEC (79)W&RS & 140RS
KANKAKEE COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE _____
DRAWN BY: KKP
CHECKED BY: JKC