

COMMITMENTS

No commitments have been made for this project.

GENERAL NOTES

Plan dimensions and details relative to existing structure have been taken from existing plans and are subject to nominal construction variations. It shall be the Contractor's responsibility to verify such dimensions and details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

All Traffic Control devices including Barricades, Barrels, or Temporary Concrete Barrier, Pavement Marking Tape, Impact Attenuator and Public Information Signs already in-place may be used during construction of this contract. Device modifications or placement shall be at the discretion of the Engineer. Contractor shall be responsible for removal of these devices at project completion. Cost to be included in Traffic Control and Protection Standard 701402.

SN.090-0069 NB. IL.116
Ramp over SB. IL.116

FILE NAME = SN090-0069 (2).dgn	USER NAME = jonesace	DESIGNED - CEJ	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	-----		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1/32" = 1' / IN.	DRAWN - CEJ	REVISED - ---		673	102-HB-211-2	TAZEWELL	17	2		
	PLOT DATE = 2/2/2009	CHECKED - ---	REVISED - ---		STEEL BEAM REPAIRS	CONTRACT NO. 68857		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT			
			DATE - -----	REVISED - ---	SCALE: -----	SHEET NO. --- OF --- SHEETS	STA. ----- TO STA. -----				