

SCHEDULE OF QUANTITIES

EPOXY PAVEMENT MARKING LINE, 4" & PAVEMENT MARKING REMOVAL

LOCATION	PVMT. MRKG. LINE, 4"		PVMT. MRKG. REM.	
	WHITE LENGTH (FOOT)	YELLOW LENGTH (FOOT)	WHITE EDGELINE (SQ.FT.)	YELLOW SKIP DASH (SQ.FT.)
JOB SITE				
TOTAL	576		576	

PAVEMENT MARKING TAPE TYPE III, 4" & WORKZONE PAVEMENT MARKING REMOVAL

LOCATION	PVMT. MRKG. TAPE, 4"		PVMT. MRKG. REM.
	WHITE LENGTH (FOOT)	YELLOW LENGTH (FOOT)	WORK ZONE PVMT. MRKG. REM. (SQ.FT.)
JOB SITE			
TOTAL	1051		350

WIDTH RESTRICTION SIGNING

LOCATION	LSUM
SHOWN ON T.C. PLAN SHEET	1
TOTAL	1

BARRIER WALL MARKERS

LOCATION	CUFT
RT.-SIDE BRIDGE PARAPET	8
TOTAL	8

TRAFFIC CONTROL

LOCATION STA. TO STA.	TEMP. CONC. BARRIER (FT)	IMPACT ATTEN. TEMP. (EACH)	T.C.&P. STANDARD 701402 (LSUM)	T.C.&P. STANDARD 701201 (LSUM)	T.C.&P. STANDARD 701601 (LSUM)	CHANGEABLE MESSAGE SIGN
Deck & T.C. Standard Length	306					
Taper Length	169					
		1	1	1	1	1
TOTAL	475	1	1	1	1	1

STEEL BEAM & DECK REPAIRS

PROTECTIVE COAT	
TOP OF DECK	SQYD
Span 1 & 2 Removal Area	
TOTAL	110.4
CONCRETE REMOVAL	
SOUTH HALF OF SPAN 2	CUYD
Span 2	
TOTAL	27.5
PROTECTIVE SHIELD	
UNDER S. HALF OF SPAN 2	SQYD
Span 2	
TOTAL	127.6
CONCRETE SUPERSTRUCTURE	
SOUTH HALF OF SPAN 2	CUYD
Span 2	
TOTAL	27.6
BRIDGE DECK GROOVING	
TOP OF DECK	SQYD
Span 1 & 2 Replacement Area	
TOTAL	77.7
FURNISHING & ERECTING STRUCTURAL STEEL	
SPAN 2	PD
Span 1 & 2 Replacement Area	
TOTAL	16,640
STUD SHEAR CONNECTORS	
SPAN 2	EA
Top Flanges	
TOTAL	504
STRUCTURAL STEEL REMOVAL	
SPAN 2	PD
Span 1 & 2 Designated Beams	
TOTAL	16,640
REINFORCEMENT BARS, EPOXY COATED	
SPAN 2 DECK	PD
Span 1 & 2 Deck Replacement	
TOTAL	6,520
ANCHOR BOLTS, 1 1/4"	
SOUTH END PIER 1	EA
Pier 1	
TOTAL	1
STRUCTURAL REPAIR OF CONCRETE (DEPTH > 5")	
PIER CAP 1	SQFT
Pier 1	
TOTAL	2.5
BEAM STRAIGHTENING	
SPAN 2, BEAM 2	LSUM
Span 2	
TOTAL	1
TEMPORARY SHORING & CRIBBING	
BEAM STRAIGHTENING DETAILS	LSUM
Jobsite Deck Support	
TOTAL	1

SN.090-0069 NB. IL.116
Ramp over SB. IL.116

FILE NAME = SN090-0069 (2).dgn	USER NAME = jonesc	DESIGNED - CEJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE. 673	SECTION 102-HB-211-2	COUNTY TAEWELL	TOTAL SHEETS 17	SHEET NO. 5
		DRAWN - CEJ	REVISED -			STEEL BEAM REPAIRS		CONTRACT NO. 68857		
		CHECKED -	REVISED -		SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		
		DATE - 01/20/2009	REVISED -		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT					