

80% FED.  
20% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000-2A	X028-2A	SFTY-2A
20200100	EARTH EXCAVATION	CU YD	1538		1538	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	270		270	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	491		491	
28100107	STONE RIPRAP, CLASS A4	SO YD	262		262	
28200200	FILTER FABRIC	SO YD	262		262	
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SO YD	753		753	
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	144		144	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	8	8		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	17193	17193		
40600300	AGGREGATE (PRIME COAT)	TON	344	344		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	5462	5462		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1200	1200		
40600990	TEMPORARY RAMP	SO YD	973	973		
40600995	TEMPORARY RAMP, SPECIAL	SO YD	1137	1137		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	10967	10932		35
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 1 3/4"	SO YD	753		753	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	287	287		
44000100	PAVEMENT REMOVAL	SO YD	753		753	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	144267	144267		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	27163	27163		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	460	460		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	493	63	430	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	142			142
44003100	MEDIAN REMOVAL	SO FT	163	163		
44004250	PAVED SHOULDER REMOVAL	SO YD	94		94	
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	18	18		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	1386	1386		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	96	96		
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	73	73		

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			824	(16-2,19X-2)RS-1,19B,19BR	Coles	49	4	
		CHECKED -	REVISED -			<b>CONTRACT NO. 74157</b>					
		DATE -	REVISED -			SCALE: N/A	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	