

STRUCTURE NUMBER 015-2023

ITEM	UNIT	QUANTITY
EARTH EXCAVATION	CU YD	1538
POROUS GRANULAR EMBANKMENT	CU YD	491
SUB-BASE GRANULAR MATERIAL, TYPE B, 6"	SQ YD	753
PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 10"	SQ YD	144
HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	753
PAVEMENT REMOVAL	SQ YD	753
COMBINATION CURB AND GUTTER REMOVAL	FOOT	430
PAVED SHOULDER REMOVAL	SQ YD	94
HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	89
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	436
PAVEMENT MARKING REMOVAL	SQ FT	441

DETECTOR LOOP, TYPE 1

STATION	LOCATION DESCRIPTION	QUANTITY (FEET)
1415+97	US 45/RUDY AVE INTERSECTION	932
TOTAL =		932

19TH ST. CONCRETE MEDIAN REPLACEMENT

STATION	SIDE	MEDIAN REMOVAL (SQ FT)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	CONCRETE MEDIAN SURFACE, 4 INCH (SQ FT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6. 12 (FOOT)
1380+40	LT	163	63	163	63
TOTALS		163	63	163	63