



STAGE I NOTES

INSTALL SIGNAGE AND ARROW BOARDS FOR NORTHBOUND LANES ACCORDING TO TRAFFIC CONTROL STANDARD 701423 AND FOR THE SOUTHBOUND LANES ACCORDING TO TRAFFIC CONTROL STANDARD 701602, CASE III.

THE TYPE III BARRICADES SHALL BE INCLUDED IN THE COST OF STANDARD 701423.

LEGEND

- DRUMS
- IMPACT ATTENUATOR
- TEMPORARY CONCRETE BARRIER WALL (STANDARD 704001)
- TYPE III BARRICADE

FILE NAME =	USER NAME = steffenk	DESIGNED -	REVISED -
c:\pwwork\pwwid\DOT\STEFFENK\dms50699\ststogel.74157.dgn		DRAWN -	REVISED -
PLOT SCALE = 20.0000 "/ IN.		CHECKED -	REVISED -
PLOT DATE = 2/9/2009		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**STAGE I CONSTRUCTION - SN 015-2023
BOX CULVERT REMOVAL AND REPLACEMENT**

SCALE: 20 SHEET NO. 1 OF 4 SHEETS STA. 1362+00 TO STA. 1374+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
824	(16-2,19X-2)RS-1,19B,19BR	Coles	49	25
CONTRACT NO. 74157				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				