

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15-2 60-15HB-2	MADISON	272	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 76624				

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE

URBAN

80% FEDERAL
20% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SEC 60-15-2			SEC 60-15HB-2			
				I000-2A		Y031-1F	X271-2A			
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3			3				
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1			1				
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	5			5				
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1				
* 88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2				
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5			5				
* 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1			1				
* 88040330	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1			1				
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	6			6				
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	132	132						
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	386	386						
M2020010	EARTH EXCAVATION	CU M	33060	33060						
M2040800	FURNISHED EXCAVATION	CU M	24190	24190						
M2070400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU M	684			684				
M2080150	TRENCH BACKFILL	CU M	131	131						
M2500100	SEEDING, CLASS 1	HA	0.6	0.6						
M2500200	SEEDING, CLASS 2	HA	2.1	2.1						
M2500210	SEEDING, CLASS 2A	HA	2.5	2.5						
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	520	520						
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	520	520						
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	520	520						
M2510115	MULCH, METHOD 2	HA	4.1	4.1						
M2510630	EROSION CONTROL BLANKET	SQ M	10485	10485						
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	2288	2288						
M2800400	PERIMETER EROSION BARRIER	METER	710	710						
M2810105	STONE RIPRAP, CLASS A3	SQ M	303			303				
M2810707	STONE DUMPED RIPRAP, CLASS A4	SQ M	927	927						
M2820200	FILTER FABRIC	SQ M	1230	927		303				
M3100300	PROCESSING LIME STABILIZED SOIL MIXTURE 300MM	SQ M	10611	10611						
M3101500	LIME	M TON	218.3	218.3						
M3112010	SUB-BASE GRANULAR MATERIAL, TYPE C	M TON	1198	1198						

10/17/2008

\$FILE\$

*Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 310 (IL 255)
SECTION 60-15-2 & 60-15HB-2
MADISON COUNTY

DRAWN BY EBB

DATE

CHECKED BY

Rev.