


F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15-2 60-15HB-2	MADISON	272	15
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 76624				




**PROPOSED TYPICAL SECTION
IL 111**
STA 30+268.699 TO STA 30+318.185

NOTES:
 TO BE REMOVED
 FOR THE LAYOUT OF THE FLUSH MEDIAN SEE DETAIL SHEETS 89-91
 THE PROPOSED PROFILE GRADE FOLLOWS THE INSIDE RIGHT EDGE OF PAVEMENT FROM STATION 30+268.699 TO STATION 30+406.199
 ■ PAVEMENT MARKING (SEE PAVEMENT MARKING PLAN SHEETS)

IL 111

STRUCTURAL DESIGN TRAFFIC:	YEAR 2014
PV = 13873	SU = 698 MU = 930
ROAD/STREET CLASSIFICATION:	CLASS I
PERCENT OF STRUCTURAL DESIGN TRAFFIC IN DESIGN LANE:	
P = 32	S = 45 M = 45
TRAFFIC FACTOR:	ACTUAL TF = 4.88 AC TYPE = 20
	MINIMUM TF = 4.27
AC GRADE:	BASE = PG 58-22 SURFACE = PG 64-22
SUBGRADE SUPPORT RATING:	SSR = POOR (STA 29+828.458 TO STA 30+600.000)



**PROPOSED TYPICAL DITCH SECTION
WITH CURB AND GUTTER
IL 111**
STA 30+297.500 TO STA 30+335.200 RT
STA 30+336.100 TO STA 30+351.600 LT

NOTES:
 * WIDTH VARIES FROM 1.6 m TO 0.0 m FROM STATION 30+297.500 TO STATION 30+327.300 RT.
 WIDTH IS 0.0 m FROM STATION 30+327.300 TO STATION 30+335.200 RT
 WIDTH IS 0.0 m FROM STATION 30+336.100 TO STATION 30+351.600 LT

PROPOSED LEGEND

- | | |
|--|--|
| <ul style="list-style-type: none"> (E1) EXISTING GROUND (R1) REMOVE EXISTING PAVEMENT WITH OVERLAY (R2) REMOVE EXISTING HOT-MIX ASPHALT OVERLAY, ± 159 mm (HMA SURF. REM. - SPECIAL) (R3) REMOVE EXISTING HOT-MIX ASPHALT SHOULDER WITH OVERLAY (SAW CUT) (R4) REMOVE EXISTING CURB AND GUTTER WITH OVERLAY (R5) REMOVE EXISTING CONCRETE MEDIAN (R6) REMOVE EXISTING AGGREGATE SHOULDER (1) HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 400 mm (HOT-MIX ASPHALT BINDER COURSE, 350 mm; HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 50 mm) (2) HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70, 38 mm (3) HOT-MIX ASPHALT BINDER COURSE, N70, FOR THICKNESS > 38 mm (4) HOT-MIX ASPHALT BASE COURSE, 300 mm (ANY WIDTH) (5) HOT-MIX ASPHALT SHOULDERS, 200 mm (6) LIME STABILIZED SOIL MIXTURE, 300 mm (7) SUBBASE GRANULAR MATERIAL, TYPE C, VARIABLE DEPTH (100 mm MINIMUM) | <ul style="list-style-type: none"> (8) AGGREGATE SHOULDER, TYPE A, 150 mm & VARIES (9) STRIP REFLECTIVE CRACK CONTROL TREATMENT (10) COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60 (11) CONCRETE MEDIAN SURFACE, 100 mm (12) CONCRETE MEDIAN, SM-15 (13) SUB-SURFACE DRAIN, STANDARD 601001 (14) AGGREGATE BASE COURSE, TYPE B, 200 mm WITH BITUMINOUS SURFACE TREATMENT, CLASS A-2 (15) COARSE AGGREGATE FILLED TO SUBGRADE (INCLUDED IN THE COST OF CONCRETE MEDIAN SURFACE) (16) BITUMINOUS MATERIALS AND AGGREGATE PRIME COATS (17) HOT-MIX ASPHALT BINDER COURSE, N70, 57 mm (18) AGGREGATE BASE COURSE, TYPE A, 200 mm (19) AGGREGATE SHOULDER, TYPE B, 200 mm & VARIES (20) CONCRETE MEDIAN, TYPE SB-15.60 (21) COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60 |
|--|--|

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
TYPICAL SECTIONS
 FAP 310 (IL 255)
 SECTION 60-15-2 & 60-15HB-2
 MADISON COUNTY
 DRAWN BY EBB
 CHECKED BY
 DATE

ALL DIMENSIONS ARE IN mm
 UNLESS NOTED OTHERWISE

5/13/2008

p:\00f1les\000024\dll111\Detail\Misc\tipsect\on015c.dgn