ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE: URBAN TOTAL QUANTITY	ROAD 100% FEDERAL J000	SIGNALS 100% FEDERAL Y031-1F
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	13	13	0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,888	4,888	0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	721	721	0
45000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	92	92	0
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	381	381	0
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8,259	8,259	0
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	584	584	0
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1,175	1,175	0
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	245	245	0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	158	158	0
78200300	PRISMATIC CURB REFLECTOR	EACH	200	200	0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	144	144	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	14	14	0
80500100	SERVICE INSTALLATION, TYPE A	EACH	2	0	2
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	158	0	158
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	641	0	641
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	324	0	324
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	10	0	10
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1	0	1
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,064	0	1,064
⊛85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	0	1

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE: URBAN TOTAL QUANTITY	ROAD 100% FEDERAL J000	SIGNALS 100% FEDERAL Y031-1F
85800100	FLASHER CONTROLLER	EACH	1	0	1
87300805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	13	0	13
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,722	0	1,722
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,536	0	1,536
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,336	0	2,336
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,919	0	1,919
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3,448	0	3,448
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	100	0	100
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	4	0	4
* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1	0	1
87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	2	0	2
87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1	0	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12	0	12
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3	0	3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	58	0	58
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4	0	4
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6	0	6
88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2	0	2
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2	0	2
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2	0	2
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2	0	2

⊛ DESIGNATES A SPECIAL PROVISION

*Specialty Items

FILE NAME = r3nfsummary4_new.dgn	USER NAME = weaverlg	DESIGNED - A. PENICK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES
		DRAWN - A. PENICK	REVISED -		
	PLOT SCALE = $SCALE$	CHECKED - A. FREY	REVISED -		
	PLOT DATE = 02/02/2009	DATE - 02/06/2009	REVISED -		SCALE: SHEET NO. 4 OF 5 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
788	520-2-2	MADISON	173	8
		CONTRACT NO. 76633		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT