ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE: URBAN TOTAL QUANTITY	ROAD 100% FEDERAL J000	SIGNALS 100% FEDERAL Y031-1F
**	88040410	SIGNAL HEAD, POLYCARBONATE, LED, 4-FACE, 1-SECTION, MAST ARM MOUNTED	EACH	1	0	1
**	88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	4	0	4
**	88200300	TRAFFIC SIGNAL BACKPLATE, PLASTIC	EACH	10	0	10
**	88500100	INDUCTIVE LOOP DETECTOR	EACH	16	0	16
**	88600100	DETECTOR LOOP, TYPE I	FOOT	2,074	0	2,074
**	88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	0	8
**	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	216	0	216
*	X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	244	244	0
*	X0321906	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	21	21	0
*	X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	10	10	0
*	X0326388	COMBINED SEWERS, CLASS A, TYPE 3, 21"	FOOT	154	154	0
*	XX000598	COMBINED SEWER REMOVAL 12"	FOOT	36	36	0
*	X0326385	COMBINED SEWER REMOVAL 21"	FOOT	154	154	0
*	XX004360	SANITARY SEWER BYPASS PUMPING	L SUM	1	1	0
*	XX005535	SEWER SPOT REPAIRS, 12"	FOOT	14	14	0
*	XX005537	SEWER SPOT REPAIRS, 18"	FOOT	20	20	0
*	X0326386	SEWER SPOT REPAIRS, 36"	FOOT	15	15	0
*	XX00554-1	CURED-IN-PLACE (CIPP), 12"	FOOT	471	471	0
*	XX005544	CURED-IN-PLACE (CIPP), 18"	FOOT	893	893	0

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE: URBAN TOTAL QUANTITY	ROAD 100% FEDERAL J000	SIGNALS 100% FEDERAL Y031-1F
*	XX005554	CURED-IN-PLACE (CIPP), 24"	FOOT	137	137	0
*	X0326387	CURED-IN-PLACE (CIPP), 36"	FOOT	702	702	0
*	XX006433	BACKFLOW PREVENTER	EACH	1	1	0
*	XX104100	CONNECTION TO EXISTING MANHOLE	EACH	11	11	0
*	X0326389	POLYUREA CURB MARKING	FOOT	67	67	0
*	X0326390	CONCRETE SLAB REMOVAL	SQ YD	414	414	0
**	X0326391	*FURNISH AND INSTALL HANDHOLE COVER	EACH	1	0	1
	X0326392	*REPAIR POLE	L.SUM	1	0	1

**Specialty Items

* DESIGNATES A SPECIAL PROVISION

FILE NAME = r3nASummary5_new.dgn	USER NAME = weaverlg	DESIGNED - A. FREY	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
		DRAWN - A. PENICK	REVISED -	
	PLOT SCALE = $SCALE$	CHECKED - A. PENICK	REVISED -	
	PLOT DATE = 02/02/2009	DATE - 02/06/2009	REVISED -	

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 5 OF 5 SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
788	520-2-2	MADISON	173	9

CONTRACT NO. 76633

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT