


BEGIN PERIMETER EROSION BARRIER STA. 32+86

NOTES:

1. TEMPORARY SEEDING QUANTITIES INCLUDE FOUR (4) TIMES ONE TOTAL COVER APPLICATION (ENTIRE CONSTRUCTION LIMITS) TYPE 1 MULCH SHALL BE USED ON ALL TEMPORARY SEEDING.
2. CLASS 2A SEEDING QUANTITIES INCLUDE ALL NON-PAVEMENT CONSTRUCTION AREAS EXCEPT THE FOLLOWING:
 - A) DETENTION BASIN (CLASS 4B)
 - B) 3:1 SIDE SLOPES FOR RIGHT SIDE OF RELOC. IL 3 (STA 775+10 TO 777+00) AND RELOC. IL 3 (STA. 790+50 TO 792+15). (CLASS 3)
3. ALL AREAS THAT ARE 3:1 OR STEEPER SHOULD BE SEEDED AND FERTILIZED USING A HYDRAULIC SEEDER.
4. EROSION CONTROL BLANKET SHALL BE USED OVER ALL PERMANENT SEEDING.

LEGEND

- SEEDING CLASS 2
- SEEDING CLASS 3
- SEEDING CLASS 4
- RIPRAP
- PERIMETER EROSION BARRIER- SILT FILTER FENCE OR OTHER AS APPROVED BY THE ENGINEER
- INLET AND PIPE PROTECTION- STRAW BALES, FILTER FABRIC, AGGREGATES, ROLLED EXCELSIOR



MATCH LINE STA. 778+00, SHEET NO. 78

FILE NAME = r3nsupp_stage3_01new.dgn	USER NAME = weaverlg	DESIGNED - A. PENICK	REVISED -
		DRAWN - A. PENICK	REVISED -
		CHECKED - A. FREY	REVISED -
		DATE - 02/06/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL PLAN
(CONSTRUCTION STAGE 3)**

SCALE: SHEET NO. 7 OF 9 SHEETS STA. TO STA.

F.A. RTE. 788	SECTION 520-2-2	COUNTY MADISON	TOTAL SHEETS 173	SHEET NO. 77
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76633	