

XXXX\$

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15-1, 60-15HB-1	MADISON	238	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
				URBAN					
				100% FEDERAL					
				SEC 60-15-1		SEC 60-15HB-1			
				J000-2A	Y031-1F	X271-2A			
M2080150	TRENCH BACKFILL	CU M	31	31					
M2500200	SEEDING, CLASS 2	HA	3.3	3.3					
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	334	334					
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	334	334					
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	334	334					
M2510115	MULCH, METHOD 2	HA	3.3	3.3					
M2510630	EROSION CONTROL BLANKET	SQ M	6160	6160					
M2800200	EARTH EXCAVATION FOR EROSION CONTROL	CU M	8	8					
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	734	734					
M2800400	PERIMETER EROSION BARRIER	METER	1058	1058					
M2810105	STONE RIPRAP, CLASS A3	SQ M	297			297			
M2810707	STONE DUMPED RIPRAP, CLASS A4	SQ M	77	77					
M2820200	FILTER FABRIC	SQ M	374	77		297			
M3020456	PROCESSING MODIFIED SOIL 300MM	SQ M	4668	4668					
M3021500	LIME	M TON	96.1	96.1					
M3112010	SUB-BASE GRANULAR MATERIAL, TYPE C	M TON	76	76					
M3511010	AGGREGATE BASE COURSE, TYPE B	M TON	4358	4358					
M3560530	HOT-MIX ASPHALT BASE COURSE WIDENING, 230MM	SQ M	372	372					
M4021010	AGGREGATE SURFACE COURSE, TYPE B	M TON	124	124					
M4021200	AGGREGATE FOR TEMPORARY ACCESS	M TON	30	30					
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	3.8	3.8					
M4060300	AGGREGATE (PRIME COAT)	M TON	9	9					
M4063085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	M TON	313	313					
M4063315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	M TON	158	158					
M4075280	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 280MM	SQ M	2325	2325					
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	53	53					
M4202235	PORTLAND CEMENT CONCRETE PAVEMENT 230MM (JOINTED)	SQ M	9726	9726					
M4205200	PROTECTIVE COAT	SQ M	16007	14029		1978			
M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	274	274					
M4240100	PORTLAND CEMENT CONCRETE SIDEWALK 100MM	SQ M	284.5	284.5					
M4248000	DETECTABLE WARNINGS	SQ M	11.3	11.3					
M4402000	PAVEMENT REMOVAL	SQ M	6305	6305					
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	1248	1248					
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	1173	1173					
M4402050	SIDEWALK REMOVAL	SQ M	120	120					
M4402390	ISLAND REMOVAL	SQ M	30	30					
M4402420	MEDIAN REMOVAL	SQ M	1404	1404					

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES FAP 310 (IL 255) SECTIONS 60-15-1, 60-15HB-1 MADISON COUNTY DRAWN BY SEB CHECKED BY
NAME	DATE	
DATE		

\$FILE\$