

XXXX\$

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15-1, 60-15HB-1	MADISON	238	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% FEDERAL						
				SEC 60-15-1		SEC 60-15HB-1				
				J000 - 2A	Y031-1F	X271-2A				
M4402530	PAVED SHOULDER REMOVAL	SQ M	1708	1708						
M4820550	HOT-MIX ASPHALT SHOULDERS, 150MM	SQ M	1115	1115						
M4820600	HOT-MIX ASPHALT SHOULDERS, 200MM	SQ M	1766	1766						
M4830230	PORTLAND CEMENT CONCRETE SHOULDERS - 230MM	SQ M	149	149						
M5010521	REMOVE EXISTING CULVERTS	METER	51	51						
M5020100	STRUCTURE EXCAVATION	CU M	889			889				
M5030290	FORM LINER TEXTURED SURFACE	SQ M	388			388				
M5030350	CONCRETE STRUCTURES	CU M	430.7			430.7				
M5030360	CONCRETE SUPERSTRUCTURE	CU M	490.0			490.0				
M5030390	BRIDGE DECK GROOVING	SQ M	1674			1674				
M5040914	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 914MM.	METER	233.7			233.7				
M5080105	REINFORCEMENT BARS	KG	140	140						
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	95230			95230				
M5090540	PIPE HANDRAIL	METER	2.6	2.6						
M5110400	SLOPE WALL (SPECIAL)	SQ M	865			865				
M5120176	FURNISHING METAL SHELL PILES 356MM X 6.35MM	METER	2000.5			2000.5				
M5120335	DRIVING PILES	METER	2000.5			2000.5				
M5200225	PREFORMED JOINT STRIP SEAL	METER	54.0			54.0				
M5403220	EXPANSION BOLTS M20	EACH	8	8						
M542C528	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 600MM RISER	EACH	1	1						
M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	1	1						
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	1	1						
M542E136	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 750MM	EACH	1	1						
M5421410	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 300MM	METER	93.5	93.5						
M5423425	PIPE CULVERTS, TYPE 2 RCCP 600MM	METER	24.5	24.5						
M5429910	CONCRETE COLLAR	CU M	2.8	2.8						
M5502840	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 300MM	METER	63.5	63.5						
M5502900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 750MM	METER	6.5	6.5						
M5510025	STORM SEWER REMOVAL 300MM	METER	26.4	26.4						
M5510060	STORM SEWER REMOVAL 600MM	METER	1.8	1.8						
M5870300	CONCRETE SEALER	SQ M	40			40				
M5930100	CONTROLLED LOW-STRENGTH MATERIAL	CU M	1.2	1.2						
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4						
M6021665	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1						
M6021711	MANHOLES, TYPE A, 1.5M DIAMETER, WITH MEDIAN INLET (604101)	EACH	1	1						
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	1246.4	1246.4						
M6062100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.15	METER	22.4	22.4						

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES FAP 310 (IL 255) SECTIONS 60-15-1, 60-15HB-1 MADISON COUNTY DRAWN BY SEB CHECKED BY
NAME	DATE	

\$FILE\$