

\$XXX\$

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15-1, 60-15HB-1	MADISON	238	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% FEDERAL							
				SEC 60-15-1		SEC 60-15HB-1					
				J000-2A	Y031-1F	X271-2A					
M6062400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-15.60	METER	41.7	41.7							
M6063600	CONCRETE MEDIAN SURFACE, 100MM	SQ M	71	71							
M6063800	CONCRETE MEDIAN, TYPE SB	SQ M	1357	1357							
M6066000	CORRUGATED MEDIAN	SQ M	1159	1159							
M7030100	SHORT-TERM PAVEMENT MARKING	METER	170	170							
M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	9	9							
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	5979	5979							
M7030250	TEMPORARY PAVEMENT MARKING - LINE 200MM	METER	192	192							
M7030260	TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	111	111							
M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	27	27							
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	690.9	690.9							
M7200100	SIGN PANEL - TYPE 1	SQ M	7.2	7.2							
M7280100	TELESCOPING STEEL SIGN SUPPORT	METER	43.6	43.6							
M7800205	PAINT PAVEMENT MARKING - LINE 100MM	METER	1469	1469							
M7800220	PAINT PAVEMENT MARKING - LINE 200MM	METER	192	192							
M7800225	PAINT PAVEMENT MARKING - LINE 300MM	METER	81	81							
M7800240	PAINT PAVEMENT MARKING - LINE 600MM	METER	11	11							
M7800600	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	9	9							
M7800605	EPOXY PAVEMENT MARKING - LINE 100MM	METER	4510	4510							
M7800625	EPOXY PAVEMENT MARKING - LINE 300MM	METER	30	30							
M7800640	EPOXY PAVEMENT MARKING - LINE 600MM	METER	16	16							
M7830100	PAVEMENT MARKING REMOVAL	SQ M	185.7	185.7							
M8030010	LOCATING UNDERGROUND CABLE	METER	122		122						
M8100250	CONDUIT IN TRENCH, 40MM DIA., PVC	METER	66.5		66.5						
M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	183.5		183.5						
M8100270	CONDUIT IN TRENCH, 65MM DIA., PVC	METER	64.5		64.5						
M8100280	CONDUIT IN TRENCH, 75MM DIA., PVC	METER	131.0		131.0						
M8100300	CONDUIT IN TRENCH, 100MM DIA., PVC	METER	9.0		9.0						
M8101070	CONDUIT PUSHED, 75MM DIA., GALVANIZED STEEL	METER	33.5		33.5						
M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	454.5		454.5						
M8710010	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 4F	METER	250		250						
M8731210	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	METER	226		226						
M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	311		311						
M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	785		785						
M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	290		290						
M8731710	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 6 PAIR	METER	368		368						
M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	METER	53		53						
M8750060	TRAFFIC SIGNAL POST, 3.35 METER	EACH	3		3						

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 310 (IL 255)
 SECTIONS 60-15-1, 60-15HB-1
 MADISON COUNTY
 DRAWN BY SEB
 CHECKED BY
 DATE

\$FILE\$