F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	60-15-1, 60-15HB-1	MADISON	238	176
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 76635

FINAL SURVEY NOTE BOOK NO.
SURVEYED
PLOTTED
TYPED
AREAS
AREAS CHECKED
BY
DATE

ORIGINAL SURVEY NOTE BOOK NO.
SURVEYED
PLOTTED
TYPED
AREAS
AREAS CHECKED
BY
DATE

GR ELEV = 196.545

197.810 197.612 197.414 VAR VAR 197.414 197.216 197.018

2.4 m

SLOPE = 4.00 %

1:2.31

1:2.06

USFL = 194.229

DSFL = 193.259

STONE DUMPED RIPRAP, CLASS A4

24.3 m 11.8 m 5.0 m

1.5 m

MANHOLE, TYPE A, 1.5 m DIAMETER, WITH MEDIAN INLET (604101)
PIPE CULVERT, RCCP, TYPE 2, 600 mm Ø, 24.3 m
PRECAST REINFORCED CONCRETE END SECTION, 600 mm, STD 542301

38+875.0

SCALE
HORIZONTAL: 1:200
VERTICAL: 1:100

PIPE SECTION - FAP 310 (IL 255) STA 38+875.0

p:\00files\00024\dhumbert\crosssections\xspipe15e.dgn