CONTRACT NO. 78002

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	*	8	5
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

*09 PAVEMENT PRESERVATION FY09-1

* WILLIAMSON/SALINE

NOTE: WHEREVER IN THESE PLANS COUNTY, CONTRACT AND SECTION ARE REFERENCED IT SHALL MEAN CONTRACT 78002, SECTION 09 PAVEMENT PRESERVATION FY09-1, AND COUNTY OF WILLIAMSON/SALINE.

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FAP 331 (IL 13) EASTBOUND LANES RURAL 100% STATE MICROSURFACING WILLIAMSON 1000 QUANTITY	FAP 331 (IL 13) EASTBOUND LANE RURAL 100% STATE MICROSURFACING SALINE 1000 QUANTITIY
X0326218	FIBER-MODIFIED ASPHALT CRACK SEAL	FOOT	101020	11840	89180
X0326221	MICRO-SURFACING, SINGLE PASS, TYPE 2	SQ YD	114537	13130	101407
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10309	1182	9127
67100100	MOBILIZATION	L SUM	1	0.4	0.6
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.4	0.6
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	5566	796	4770
70300210	TEMPORARY PAVEMENT MARKING, LETTERS & SYMBOLS	SQ FT	436.8	36.4	400.4
70300220	TEMPORARY PAVEMENT MARKING, LINE 4"	FOOT	55517	6469	49048
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3286	367	2919
• 78000100	THERMOPLASTIC PAVEMENT MARKING, LETTERS & SYMBOLS	SQ FT	436.8	36.4	400.4
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	55517	6469	49048
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	333	44	289
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	333	44	289
78300105	PAVEMENT MARKING REMOVAL	FOOT	55,517	6,469	49,048

• SPECIALTY ITEM

Rev. 4-15-09

FAP 331 (IL 13) SUMMARY OF QUANTITIES

PLOT DATE = 12/29/2008
FILE NAME = c:\pw_work\PWIDOT\MCCORDKR\dms43884\d978882-sht-mao.dgn
PLOT SCALE = 1584.0000 ' / IN.
USER NAME = mccordkr