

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONST. CODE 1000 TOTAL QUANTITY
20700110	POROUS GRANULAR EMBANKMENT	TON	300
20800150	TRENCH BACKFILL	CU YD	39
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	822
* 21400100	GRADING AND SHAPING DITCHES	FOOT	232
28100107	STONE RIP RAP, CLASS A4	SQ YD	6
28200200	FILTER FABRIC	SQ YD	6
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3010
40600300	AGGREGATE (PRIME COAT)	TON	65
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	360
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	330
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1320
* 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	103
42400800	DETECTABLE WARNINGS	SQ FT	96
* 44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	1866
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	23
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	97
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	1550
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	258
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	2
54247200	GRATING FOR CONCRETE FLARED END SECTION 54"	EACH	2
550A0200	STORM SEWERS, CLASS A, TYPE 1 54"	FOOT	53
55102000	STORM SEWER REMOVAL 54"	FOOT	70
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1
* 60252710	CATCH BASINS TO BE ADJUSTED WITH SPECIAL FRAME AND GRATE	EACH	1
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1
67100100	MOBILIZATION	L SUM	1
* 70101800	TRAFFIC CONTROL AND PROTECTION, SPECIAL	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2640
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	886
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20758
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	327
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14
* X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	5
* X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	120
* XX006425	RESTORATION	SQ YD	1066
* Z0064000	SCARIFYING AND REGRADING EXISTING ASPHALT SURFACE	SQ YD	14950

Δ SPECIALTY ITEMS
* SEE SPECIAL PROVISIONS

Plotted: Feb 03, 2009 @ 11:07am - Plotted By: TJohnson - Tab: 03-SUM QUANT (22-34)

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.

	Engineering Enterprises, Inc. Consulting Engineers 52 Wheeler Road Sugar Grove, Illinois 60554 630/466-9350
	UNITED CITY OF YORKVILLE 800 GAME FARM ROAD YORKVILLE, ILLINOIS 60560

NO.	DATE	REVISIONS
1	01/28/09	PER IDOT REVIEW

FOX ROAD LAPP IMPROVEMENTS

SUMMARY OF QUANTITIES

DATE:	SEPT, 2008
PROJECT NO:	Y00815
FILE NO:	Y00815-CVR
SHEET	3 OF 20

PATH = H:\S055620\Y00815\dwg\Y00815-Cvr.dwg