

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY 1000-2A	STRUCT X081-2A	BOX CULVERT X028-2A	HWY LIGHTING Y030-1E
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	470	470			
44000400	GUTTER REMOVAL	FOOT	7237	7237			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	791	791			
44004300	PAVEMENT BREAKING	SQ YD	831	831			
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	1565	1565			
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	147	147			
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	329	329			
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	1782	1782			
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	687	687			
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	1434	1434			
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	42030	42030			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2483	2483			
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	13161	13161			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	910	910			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1			
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1			
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1			
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1			
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1		1		
50104300	CONCRETE HEADWALL REMOVAL	CU YD	120	120			

* SPECIALTY ITEM

FILE NAME = miscsheets.dgn	USER NAME = ghdreem	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -	665			(136,137)W&RS-3d136Rd109BR-2	HENDERSON	9		
PLOT DATE = 3/17/2009	CHECKED -	REVISED -	CONTRACT NO. 88773			ILLINOIS FED. AID PROJECT				
	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.			