

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FEDERAL	80% FEDERAL	80% FEDERAL	80% FEDERAL
				20% STATE	20% STATE	20% STATE	20% STATE
				ROADWAY	STRUCT	BOX CULVERT	HWY LIGHTING
				I000-2A	X081-2A	X028-2A	Y030-1E
* 78200305	PRISMATIC BARRIER REFLECTOR	EACH	12	12			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	22	22			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	10	10			
* 80400105	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1				1
* 82103900	LUMINAIRE, SODIUM VAPOR, MULT 1-MOUNT, 250 WATT	EACH	2				2
* A2002816	TREE, CATALPA SPECIOSA (NORTHERN CATALPA), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5			
* A2005016	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2" CALIPER, BALLED AND BURLAPPED	EACH	7	7			
* A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	10	10			
X0301007	INLET-MANHOLE, TYPE G-1, 4'-DIAMETER, SPECIAL	EACH	1	1			
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	565	565			
* X0320678	TREE WHIP MIXTURE	EACH	146	146			
X0322729	MATERIAL TRANSFER DEVICE	TON	14526	14526			
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	18	18			
X0323660	DROP BOX NO.1	EACH	1	1			
X0323661	DROP BOX NO.2	EACH	1	1			
X0323662	DROP BOX NO.3	EACH	1	1			
X0323663	DROP BOX NO.4	EACH	1	1			
X0323664	DROP BOX NO.5	EACH	1	1			
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	3034	3034			
X0324990	DROP BOX NO.6	EACH	1	1			
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	70	70			
X0545000	BOX CULVERT REMOVAL	FOOT	337	337			
X0712400	TEMPORARY PAVEMENT	SQ YD	1301	1301			

* SPECIALTY ITEM