

TREE REMOVAL				
LOCATION	NO. OF TREES	6 TO 15 UNITS DIAMETER (1" DIAMETER = 1 UNIT)	OVER 15 UNITS DIAMETER (1" DIAMETER = 1 UNIT)	ACRES
EXISTING REST AREA	SEE REMOVAL SHEET	108.2	186.1	
RT. STA. 20+00	1		22.4	
RT. STA. 21+00	1		39.2	
RT. STA. 30+00 TO 50+00				0.6
RT. STA. 52+00	1		23.2	
RT. STA. 54+00	1		42	
RT. STA. 56+00	1		28.1	
RT. STA. 71+75	1		41.5	
RT. STA. 76+00	1		31.9	
RT. STA. 77+25	1		37	
RT. STA. 78+25	1		36.2	
RT. STA. 78+75	1		33.8	
LT. STA. 98+50	25			0.058
RT. STA. 98+50	24			0.038
LT. STA. 111+00 TO 114+00				0.23
LT. STA. 117+50	1		34.9	
RT. STA. 122+50 TO 131+50				0.85
LT. STA. 122+50 TO 125+50				0.73
RT. STA. 140+50	1		30	
RT. STA. 140+50 TO 141+50	5	43.2		
RT. STA. 149+00	1		28	
RT. STA. 150+50 TO 163+00				0.63
LT. STA. 151+50 TO 156+00				0.49
LT. STA. 178+00	2 STUMPS		44.5	
LT. STA. 179+00	1 STUMP		23	
RT. STA. 183+00	7 EVERGREENS	79.6		
LT. STA. 183+00	2		52	
LT. STA. 185+00	3		109	
LT. & RT. STA. 211+27 TO 223+65				0.5
TOTAL	23	231	843	4.13

UNSUITABLE MATERIAL					
LOCATION	LENGTH	DEPTH	WIDTH	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL, SPECIAL
	FOOT	FOOT	FOOT	CU. YD.	CU. YD.
AT CULVERTS					
STA. 4+80.00	94.3	1.5	6.67	34.9	
STA. 24+00.00	83	1.5	6.67	30.8	
LT. STA. 36+05.86	23	1.5	7.67	9.8	
RT. STA. 36+05.86	22.1	1.5	7.67	9.4	
RT. STA. 36+05.86	SEE DROP BOX DETAIL			2.0	
STA. 42+00.00	84	1.5	7.67	35.8	
STA. 58+05.00	86	1.5	6.67	31.9	
LT. STA. 71+06.15	22.3	1.5	6.67	8.3	
RT. STA. 71+06.15	18.1	1.5	6.67	6.7	
STA. 75+24.85	86	1.5	6.67	31.9	
STA. 77+56.14	86	1.5	6.67	31.9	
STA. 80+48.74	86	1.5	6.67	31.9	
STA. 84+56.42	88.5	1.5	6.67	32.8	
LT. STA. 94+15.99	21.1	1.5	6.67	7.8	
RT. STA. 94+15.99	17.8	1.5	6.67	6.6	
LT. STA. 98+00	SEE BOX CULVERT DETAIL			201.6	
RT. STA. 98+00	SEE BOX CULVERT DETAIL			167.1	
LT. STA. 112+47.02	36.6	1.5	7.67	15.6	
RT. STA. 112+47.02	12.9	1.5	7.67	5.5	
RT. STA. 112+47.03	SEE DROP BOX DETAIL			2.0	
LT. STA. 124+21.91	SEE BOX CULVERT DETAIL			233.2	
RT. STA. 124+21.91	SEE BOX CULVERT DETAIL			139.9	
LT. STA. 153+74.76	20.7	1.5	8.83	10.2	
RT. STA. 153+74.76	21.3	1.5	8.83	10.4	
RT. STA. 153+74.77	SEE DROP BOX DETAIL			2.7	
LT. STA. 155+19.78	SEE BOX CULVERT DETAIL			156.4	
RT. STA. 155+19.78	SEE BOX CULVERT DETAIL			200.8	
LT. STA. 178+23.90	22.3	1.5	7.67	9.5	
RT. STA. 178+23.90	18.6	1.5	7.67	7.9	
RT. STA. 178+23.91	SEE DROP BOX DETAIL			2.0	
LT. STA. 184+00.12	13.9	1.5	6.67	5.2	
RT. STA. 184+00.12	12	1.5	6.67	4.4	
RT. STA. 184+00.12	SEE DROP BOX DETAIL			1.4	
RT. STA. 221+24.61	SEE DROP BOX DETAIL			1.4	
UNDER PAVEMENT AT VIADUCT					
STA. 217+00 TO 218+55	155	1	30.166		173
STA. 218+55 TO 219+05	50	1.5	30.166		84
STA. 219+05 TO 222+00	295	1	30.166		330
TOTAL				1490	587

* Quantity calculated in CADD

LOCATION	LENGTH	NO. OF LANES	EXPLORATION TRENCH 48" DEPTH	EXPLORATION TRENCH, SPECIAL
			FEET	FEET
STA. 117+00 TO 133+00	1600	2		3200
STA. 157+25 TO 163+25	600	2		1200
STA. 217+50 TO 220+85	335	2	670	
TOTAL			670	4400

FILE NAME = shv01.dgn	USER NAME = ghdnsam	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
665	(136,137)W&RS-3;136R109BR-2	HENDERSON		19
CONTRACT NO. 88773				
ILLINOIS FED. AID PROJECT				