

PERMANENT AND TEMPORARY PAVEMENT MARKINGS														
LOCATION	NO PASING ZONE NOTES*	LENGTH	TEMPORARY					EPOXY					PAINT	
			4" WHITE		4" YELLOW		8" WHITE	12" WHITE DIAG	12" YELLOW DIAG	24" WHITE STOP BAR	LETTERS AND SYMBOLS	4" YELLOW CL		
			LT FOOT	RT FOOT	DASH FOOT	SOLID FOOT	DBL FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	
IL 116														
2+93 TO 10+30	SEE PMK DETAIL	737	829	802			1706	499	354	109		40.8	31.2	
10+30 TO 15+96	NPZ EB & WB	566	566	566			1132							
15+96 TO 26+89	NPZ WB	1093	1093	1093	274	1093								
26+89 TO 41+04	NONE	1415	1415	1415	354									
41+04 TO 51+00	NPZ EB	996	996	996	249	996								
51+00 TO 61+50	NPZ WB	1050	1050	1050	263	1050								
61+50 TO 71+68	NONE	1018	1018	1018	255									
71+68 TO 82+00	NPZ EB	1032	1032	1032	258	1032								
82+00 TO 88+00	NPZ EB & WB	600	600	600			1200							
88+00 TO 96+00	NPZ WB	800	800	800	200	800								
96+00 TO 97+08	NPZ EB & WB	108	108	108			216							
97+08 TO 107+00	NPZ EB	992	992	992	248	992								
107+00 TO 146+00	NPZ EB & WB	3900	3900	3900			7800							
146+00 TO 153+77	NPZ WB	777	777	777	195	777								
153+77 TO 157+20	NPZ EB & WB	343	343	343			686							
157+20 TO 162+00	NPZ EB	480	480	480	120	480								
162+00 TO 163+23	NONE	123	123	123	31									
163+23 TO 173+20	NPZ WB	997	997	997	250	997								
173+20 TO 194+02	NONE	2082	2082	2082	521									
194+02 TO 201+08	NPZ EB	706	706	706	177	706								
201+08 TO 223+63	NPZ EB & WB	2255	2255	2255			4510							
IL 94														
284+70 TO 298+00	SEE PMK DETAIL	1330	1008	1330		563	3702	280		424		62.4		
County Highway 9		21161												5291
SUB TOTALS			23170	23465	3395	9486	20952		354	533				
TOTALS			80468				779		887	41	94			5291

* All No Passing Zones shall be verified by the Resident Engineer before striping.

TRAFFIC PROTECTION FOR CULVERT EXTENSIONS				
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS	IMPACT ATTENUATORS
			TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	RELOCATE (FULLY REDIRECTIVE) TEST LEVEL 3
	FOOT	FOOT	EACH	EACH
97+39 TO 98+09	70		2	
98+17 TO 98+57		40		2
123+59 TO 124+59	100		2	
123+85 TO 124+85		100		2
154+55 TO 155+35	80		2	
155+01 TO 155+81		80		2
TOTAL	250	220	6	6

LOCATION	TEMPORARY PAVEMENT	TEMPORARY PAVEMENT REMOVAL
	SQ YD	SQ YD
North Temp Pav't		
6+63 TO 11+91	468.6	468.6
11+91 TO 12+18		26.1
12+18 TO 12+91	34.3	34.3
South Temp Pav't		
6+25 TO 11+91	715.7	715.7
11+91 TO 12+18		38.1
12+18 TO 12+91	82.2	82.2
TOTAL	1301	1363

SHORT TERM PAVEMENT MARKING				PAVEMNT MARKING TAPE, TYPE III 4 INCH	WORK ZONE PAVEMENT MARKING REMOVAL
LOCATION	LENGTH	DASH	ALL APPS		
	FOOT	FOOT	FOOT	FOOT	SQ FT
IL 116					
5+30 TO 223+63	21833	4366.6			
X 3 APPLICATIONS				13099.8	
TEE CONSTRUCTION STAGES II & III (IL 116)				2864	SHORT TERM PAV'T
TEE CONSTRUCTION STAGES II & III (IL 94)				800	MARKING
TEE CONSTRUCTION STAGE IV (IL 116)				2864	AND
TEE CONSTRUCTION STAGE IV (IL 94)				1212	PAV'T
CULVERT REPLACEMENT 12+03.79				1932	MARKING
CULVERT REPLACEMENT 24+05.10				1880	TAPE
CULVERT REPLACEMENT 42+05.22				1884	X 1/3
CULVERT REPLACEMENT 58+10.10				1876	(WIDTH)
CULVERT REPLACEMENTS 75+24.85 TO 84+56.42				5616	
TOTAL			13100	20928	11343

TRAFFIC CONTROL AND PROTECTION STANDARD 701316 (SPECIAL)		TEMPORARY BRIDGE TRAFFIC SIGNALS	
LOCATION	EACH	LOCATION	EACH
12+03.79	1		1
24+05.10	1		1
42+05.22	1		1
58+10.10	1		1
75+24.85			
77+56.14	1		1
80+48.74			
84+56.42			
TOTAL	5		5

RAISED REFLECTIVE PAVEMENT MARKERS		
LOCATION	LENGTH	2 WAY AMBER
	FOOT	EACH
IL 116 - centerline		
213+32 TO 223+63	1031	26
TOTAL		26

TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	
LOCATION	EACH
County Highway 8 closure	1
IL 94 closure	1
IL 116 closure	1
TOTAL	3

LOCATION	TRAFFIC CONTROL SURVEILLANCE CAL DA
JOBSITE	120
TOTAL	120

TRAFFIC CONTROL AND PROTECTION, STANDARD							
LOCATION	701201	701306	701326	701336	701501 (SPECIAL)	BLR 21	
	L SUM	L SUM	L SUM	L SUM	L SUM	L SUM	L SUM
JOBSITE	1	1	1	1	1	1	1
TOTAL	1	1	1	1	1	1	1