

LT. & RT. STA. 275+00 TO 279+00 LT. & RT. STA. 284+00 TO 289+35 LT. & RT. STA. 297+00 TO 298+50 (STA. 298+50 - IDOT PLANS END & CONSULTANT PLANS BEGIN)

LT. & RT. STA. 279+00 TO 284+00 LT. & RT. STA. 289+35 TO 297+00

## REMOVAL NOTES

- 1 (11) BEGINS STA. 291+57 AND ENDS STA. 292+86
- 2 STA. 292+86 TO 294+18.7 PAVEMENT BREAKING
- 3 STA. 294+18.7 TO 298+50 EXISTING PAVEMENT TO REMAIN IN PLACE.

## EXISTING LEGEND

- 1 9-6-9 PCC PAVEMENT
- 2) 5"± HMA OVERLAY'S
- (3) 8" HMA BASE CSE. WIDENING WITH 3" OVERLAY
- 4 6" HMA SHOULDER CURRENTLY BEING USED AS WIDENING TO BE REMOVED (PAID AS PAVEMENT REMOVAL)
- (5) AGG. SHOULDER
- 6 BURIED GUTTER & HMA OVERLAY TO BE REMOVED (PAID AS PAVEMENT REMOVAL, SPECIAL)
- 7 TYPE A MODIFIED GUTTER TO BE REMOVED
- (8) TYPE B MODIFIED GUTTER TO BE REMOVED
- (9) GUTTER TO BE REMOVED (UNKNOWN TYPE)
- (10) CURB & GUTTER, TY B-6.24 TO BE REMOVED
- (11) PAVEMENT REMOVAL (SEE SPECIAL PROVISIONS)

## NOTES

- (1'-0" OF THE ORIGINAL 9-6-9 PAVEMENT SHALL BE REMOVED AT LOCATIONS SPECIFIED TO ESTABLISH CLEAN EDGE FOR PROPOSED WIDENING.)
- HMA SURFACE REMOVAL IS SHOWN ON PROP. TYPICALS

FILE NAME =	USER NAME = noltera	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS	EXISTING TYPICAL SECTIONS — IL 94		F.A. RTE.	SECTION	COUNTY TOTAL SHEETS NO
	PLOT SCALE = 100.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION			_		CONTRACT NO.
	PLOT DATE = 1/29/2009	DATE -	REVISED -		SCALE: SHEET NO. OF SHI	HEETS STA. TO STA.	FED. ROAD DIST.	NO. ILLINOIS FED. AI	ID PROJECT