

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FED 20% STATE F.A.P. 781 (IL. RTE. 33)	
				4+920.234 TO 15+545.000	15+545.000 TO 16+016.000
				CONSTRUCTION CODE TYPE	
				I000-2A RURAL	I000-2A URBAN
M4060300	AGGREGATE (PRIME COAT)	M TON	279	267	12
M4060895	CONSTRUCTING TEST STRIP	EACH	3	3	0
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	447	278	169
M4060990	TEMPORARY RAMP	SQ M	60	43	17
M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	4,954	4,705	249
M4063340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	8,199	7,833	366
M4075350	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 350MM	SQ M	6,984	6,984	0
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	1,851	1,517	134
M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	333	333	0
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	1,471	1,471	0
M4400715	HOT-MIX ASPHALT SURFACE REMOVAL, 15MM	SQ M	66,450	63,038	3,412
M4400740	HOT-MIX ASPHALT SURFACE REMOVAL, 40MM	SQ M	4,479	4,479	0
M4400950	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ M	8,339	8,339	0
M4402000	PAVEMENT REMOVAL	SQ M	5,263	5,263	0
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	5,864	5,461	403
M4405000	PAVED DITCH REMOVAL	METER	871	871	0
M4420300	PAVEMENT PATCHING, TYPE I 300MM	SQ M	188	168	20
M4422300	PAVEMENT PATCHING, TYPE II 300MM	SQ M	100	90	10
M4812150	AGGREGATE SHOULDERS, TYPE B, 150MM	SQ M	25,534	24,298	1,236
M4820550	HOT-MIX ASPHALT SHOULDERS, 150MM	SQ M	19,583	18,789	794
M5010521	REMOVE EXISTING CULVERTS	METER	84	75	9
M5010522	PIPE CULVERT REMOVAL	METER	1,966	1,841	125
M5030350	CONCRETE STRUCTURES	CU M	3.9	3.9	0.0
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	130	130	0
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	690	690	0
M5401002	PRECAST CONCRETE BOX CULVERT 600MM x 450MM	METER	15.1	15.1	0.0
M5401005	PRECAST CONCRETE BOX CULVERT 600MM x 600MM	METER	5.7	5.7	0.0
M5401010	PRECAST CONCRETE BOX CULVERT 900MM x 600MM	METER	5.7	5.7	0.0
M5402020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M (M273)	METER	30.6	30.6	0.0
M5403220	EXPANSION BOLTS M20	EACH	161	161	0
M5421210	PIPE CULVERTS, TYPE 1 RCCP, 375MM	METER	126.5	110.0	16.5
M5421215	PIPE CULVERTS, TYPE 1 RCCP, 450MM	METER	47.5	35.0	12.5
M5421225	PIPE CULVERTS, TYPE 1 RCCP, 600MM	METER	118.5	118.5	0.0

* SEE SPECIAL PROVISIONS

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SUMMARY OF QUANTITIES</p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE DECEMBER 22, 2008 CHECKED BY LWJ</p>

PLOT DATE = 1/29/2009
 FILE NAME = H:\1420\Contract 94533\SHT_004_sump_V8.dgn

H. M. & G. NO. 4420