SUMMARY OF QUANTITIES

Item No.	Description	Unit	As Bid	Record Paid
AR107812	L-807 W C - 12' Internally Lit	Each	1.0	
AR108158	1/C #8 5KV UG Cable in UD	Linear Foot	4,330.0	and a second
AR108960	Remove Cable	Linear Foot	645.0	
AR125410	MITL-Stake Mounted	Each	6.0	
AR125415	MITL-Base Mounted	Each	2.0	
AR125443	Taxi Guidance Sign, 3 Character	Each	1.0	
AR125444	Taxi Guidance Sign, 4 Character	Each	1.0	
AR125961	Relocate Stake Mounted Light	Each	2.0	
AR150510	Engineer's Field Office	Lump Sum	1.0	
AR150540	Haul Route	Lump Sum	1.0	
AR152410	Unclassified Excavation	Cubic Yard	3,920.0	Early State Control
AR152441	On-Site Borrow	Cubic Yard	1,555.0	
AR156520	Inlet Protection	Each	3.0	
AR209606	Crushed Agg. Base Course - 6"	Square Yard	6,200.0	
AR501510	10" PCC Pavement	Square Yard	5,965.0	
AR501530	PCC Test Batch	Each	1.0	
AR620525	Pavement Marking-Black Border	Square Foot	1,695.0	
AR620530	Pavement Marking-Epoxy	Square Foot	1,695.0	
AR705412	Porous Backfill No. 2	Cubic Yard	80.0	
AR705506	6" Perforated Underdrain	Linear Foot	970.0	
AR705640	Underdrain Cleanout	Each	3.0	
AR800922	Cable - Circuit C3	Linear Foot	1,075.0	
AR901510	Seeding	Acre	4.4	
AR905510	Topsoiling (From On Site)	Cubic Yard	2,360.0	
AR908510	Mulching	Acre	4.4	

LE040



HANSON PROFESSIONAL SERVICES INC.

815 Commerce Drive, Suite 200 Oak Brook, Illinois 60523 Telephone: 630.990,3800 Fax: 630.990,3801

Illinois Professional Design Firm Registration No. 184—001084

© Copyright Hanson Professional Service Inc. 2008



JOLIET REGIONAL PORT DISTRICT

1 George Michas Drive Romeoville, Illinois 60446 Telephone: 815.838.9497 Fax: 815.838.9524

COMPLETE TAXIWAY G

AIP PROJECT NO. 3-17-0140-B43 IDA PROJECT NO. LOT-3883

			T
			1
			Г
			Г
No.	Drawing Issue Description	Date	Ву

Date

JANUARY 30, 2009

Sheet Title

SUMMARY OF QUANTITIES

08A0122	
Project Number	
LDH	01/30/09
Layout By	Date
LDH	01/30/09
Designed By	Date
RMH	01/30/09

2

Sheet No.