LE040

UNDERDRAIN SCHEDULE

Structure	Station	Offset	Type	Rim El.	Invert El.	Pay Length	Slope %
U1	250+03.05	33.40 LT	Clean Out	--	657.54		
						322.5	0.30
U2	253+25	26.50 LT	Slope Break	--	656.57		
						5.0	--
U3	253+30	26.50 LT	RCP Connection	--	645.88		
						5.0	--
U4	253+35	26.50 LT	Slope Break	--	657.17		
						155.0	0.30
U5	254+90	26.50 LT	Clean Out	659.55	657.63		
U6 (Existing)	250+09.90	26.50 RT	Meet Existing	--	657.42		
						315.0	0.30
U7	253+25	26.50 RT	Slope Break	--	656.48		
						5.0	--
U8	253+30	26.50 RT	RCP Connection	--	645.72		
						5.0	--
U9	253+35	26.50 RT	Slope Break	--	657.17		
						155.0	0.30
U10	254+90	26.50 RT	Clean Out	659.55	657.63		

HANSON

HANSON PROFESSIONAL SERVICES INC.

815 Commerce Drive, Suite 200
Oak Brook, Illinois 60523
Telephone: 630.990.3800
Fax: 630.990.3801

Illinois Professional Design Firm
Registration No. 184-001084

© Copyright Hanson Professional Service Inc. 2008

Chicago-Romeoville Airport

JOLIET REGIONAL PORT DISTRICT

1 George Michas Drive
Romeoville, Illinois 60446
Telephone: 815.838.9497
Fax: 815.838.9524

COMPLETE TAXIWAY G

AIP PROJECT NO. 3-17-0140-B43
IDA PROJECT NO. LOT-3883

No.	Drawing Issue Description	Date	By

Date
JANUARY 30, 2009

Sheet Title
UNDERDRAIN SCHEDULE

08A0122
Project Number

LDH 07/01/08
Layout By Date

LDH 07/01/08
Designed By Date

RMH 01/30/09
Reviewed By Date

LDH | ---- | ----
Drawn By

12
Sheet No.

I:\08JOBS\08040\08A0122\DRAWINGS\SHEETS\12-UNDERDRAIN SCHEDULE.DWG FEB 27, 2009 11:02AM HAUSKO0082