LI031

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR125470	MODIFY EXISTING SIGN PANEL	EACH	2	
AR108656	3/C #6 600V UG CABLE IN UD	L.F.	5740	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1	
AR125620	ABBREVIATED PAPI (L-881 SYSTEM)	EACH	2	
AR125909	REMOVE VASI	EACH	2	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152480	SHOULDER ADJUSTMENT	S.Y.	2,844	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	1,429	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	210	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	590	
AR402622	POROUS FRICTION COURSE, 0.10'	S.Y.	33,634	
AR603510	BITUMINOUS TACK COAT	GAL.	8,409	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	19,522	
AR620525	PAVEMENT MARKING - BLACK BORDER	S.F.	375	
AR751949	ADJUST INSPECTION HOLE	EACH	1	
AR901510	SEEDING	ACRE	0.6	
AR908520	EXCELSIOR BLANKET	S.Y.	2,844	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN STA. 10+00 TO STA. 25+00
5	PROPOSED CONSTRUCTION PLAN STA. 25+00 TO STA. 41+00
6	PROPOSED CONSTRUCTION PLAN STA. 41+00 TO STA. 49+00
7	PROPOSED MARKING PLAN (RWY 9-27) STA. 10+00 TO STA. 35+90
8	PROPOSED MARKING PLAN (RWY 9-27) STA. 35+90 TO STA. 49+00
9	EXISTING ELECTRICAL PLAN RUNWAY 9 END
10	EXISTING ELECTRICAL PLAN RUNWAY 27 END
11	PROPOSED ELECTRICAL PLAN FOR RUNWAY END 9
12	PROPOSED ELECTRICAL PLAN FOR RUNWAY END 27
13	PROPOSED PAPI DETAILS AND NOTES RUNWAY 9 END
14	PROPOSED PAPI DETAILS AND NOTES RUNWAY 27 END
15	ELECTRICAL LEGEND AND ABBREVIATIONS
16	ONE-LINE DIAGRAM FOR RWY 9-27 PAPI UNITS
17	AIRFIELD LIGHTING WIRING SCHEMATIC
18	LIGHTING CONTACTOR PANEL DETAIL
19	PAPI FIELD WIRING CONNECTIONS
20	ELECTRICAL DETAILS SHEET 1
21	ELECTRICAL DETAILS SHEET 2
22	ELECTRICAL NOTES SHEET 1
23	ELECTRICAL NOTES SHEET 2

DATE	REVISION	BY

LITCHFIELD MUNICIPAL AIRPORT
LITCHFIELD, ILLINOIS

IL. PROJ.: 3LF-3559 A.I.P. PROJ.: 3-17-0063-B13

HEI Project No. 814-06RWYD 0800
Filename R-002FLP.DWG
Scale NOT TO SCALE
Date 01/29/08

LAYOUT	B.A.K.	12/05/05
DRAWN	B.A.K.	12/05/05
REVIEWED	C.A.H.	01/29/08

HANSON

Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

PROPOSED P.F.C.
ON RUNWAY 9-27

SUMMARY OF QUANTITIES
AND
INDEX TO SHEETS

2

APR 11, 2008 10:26 AM HAGLOOG382
I:\AIRPORTS\LITCHFIELD\814-06RWY\AIRPORT\SHEETS\R-002FLP.DWG - Layout1