


LI031

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

CALL J.U.I.E. FOR UTILITY INFORMATION AT 1-800-892-0123.

- LEGEND**
- — — — — EXISTING PAVEMENT
 - - - - - EXISTING AIRFIELD LIGHTING POWER CABLE
 - - - - - EXISTING REIL POWER AND CONTROL CABLES
 - EXISTING STAKE MOUNTED RUNWAY LIGHT
 - ⊙ EXISTING STAKE MOUNTED RUNWAY THRESHOLD LIGHT
 - ▷ EXISTING REIL
 - ▣ EXISTING BASE MOUNTED RUNWAY LIGHT
 - ⊕ EXISTING BASE MOUNTED RUNWAY THRESHOLD LIGHT
 - PROPOSED 3/C #6 600V UG CABLE IN UNIT DUCT (PAPI POWER CABLES)
 - ▨ PROPOSED PAPI UNIT



0' 15' 30' 60'
 FULL SIZE SCALE: 1" = 30'
 HALF SIZE SCALE: 1" = 60'

	REVISION	DATE	BY
LITCHFIELD MUNICIPAL AIRPORT LITCHFIELD, ILLINOIS			
ILL. PROJ.: 3LF-3559 A.I.P. PROJ.: 3-17-0063-B13		HEL Project No. 814-06RWYD_0800 Filename: R-142ELE.DWG Scale: 1"=30' Date: 01/29/08	
LAYOUT DRAWN REVIEWED	MDR MDR CAH/KNL	01/15/08 01/15/08 01/29/08	
 Hanson Professional Services Inc. 1245 Springfield, Illinois 62703-2686 Offices Nationwide			
PROPOSED P.F.C. ON RUNWAY 9-27		PROPOSED ELECTRICAL PLAN FOR RUNWAY END 9	
11			