

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITIES	
			AS AWARDED	AS BUILT
BASE BID:				
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	8,540	
AR108258	2/C #8 5 KV UG CABLE IN UD	L.F.	3,580	
AR108962	REPLACE CABLE	L.F.	950	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	670	
AR110901	CONCRETE DUCT REMOVAL	L.F.	260	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	2	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	2	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	2	
AR125510	MIRL, BASE MOUNTED	EACH	2	
AR125520	HIRLQ, BASED MOUNTED	EACH	1	
AR125565	SPLICE CAN	EACH	2	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	7	
AR125903	REMOVE INPAVEMENT LIGHT	EACH	1	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	8	
AR125942	ADJUST BASE MOUNTED LIGHT	EACH	7	
AR125944	ADJUST TAXI GUIDANCE SIGN	EACH	2	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	68	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR151450	CLEARING AND GRUBBING	ACRE	2.5	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	15,825	
AR152441	ON-SITE BORROW	C.Y.	34,800	
AR152442	OFFSITE BORROW EXCAVATION	C.Y.	46,600	
AR156500	TEMPORARY EROSION CONTROL	L.S.	1	
AR156540	RIPRAP	S.Y.	410	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	16,795	
AR209600	GEOTEXTILE FABRIC	S.Y.	20,641	
AR401610	BITUMINOUS SURFACE COURSE	TON	6,140	
AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	1	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	1,175	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	14,900	
AR501512	12" PCC PAVEMENT	S.Y.	20,124	
AR501530	PCC TEST BATCH	EACH	1	
AR501540	PCC PAVEMENT GROOVING	S.Y.	9,345	
AR501900	REMOVE PCC PAVEMENT	S.Y.	10,800	
AR602510	BITUMINOUS PRIME COAT	GAL.	3,735	
AR603510	BITUMINOUS TACK COAT	GAL.	123	

SUMMARY OF QUANTITIES, CONTINUED

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITIES	
			AS AWARDED	AS BUILT
BASE BID (CONTINUED):				
AR620510	PAVEMENT MARKING	S.F.	9,700	
AR701442	42" RCP, CLASS III	L.F.	535	
AR701512	12" RCP, CLASS IV	L.F.	126	
AR701524	24" RCP, CLASS IV	L.F.	895	
AR701713	RCEP SPAN 30 RISE 19	L.F.	302	
AR701900	REMOVE PIPE	L.F.	160	
AR705506	6" PERFORATED UNDERDRAIN	L.F.	3,108	
AR751410	INLET	EACH	1	
AR751415	INLET-SPECIAL	EACH	4	
AR751540	MANHOLE 4'	EACH	2	
AR751550	MANHOLE 5'	EACH	5	
AR751560	MANHOLE 6'	EACH	1	
AR751570	MANHOLE - SPECIAL	EACH	4	
AR751903	REMOVE MANHOLE	EACH	2	
AR751906	REMOVE CATCH BASIN	EACH	1	
AR751945	ADJUST MANHOLE - NON PAVEMENT	EACH	2	
AR751963	RELOCATE MANHOLE	EACH	1	
AR752424	PRECAST REINFORCED CONC. FES 24"	EACH	1	
AR752442	PRECAST REINFORCED CONC. FES 42"	EACH	1	
AR752724	P R CONC. FES EQ. ROUND SIZE 24"	EACH	1	
AR752900	REMOVE END SECTION	EACH	1	
AR801605	REPLACE TAXI GUIDANCE SIGN PANEL	EACH	60	
AR801628	RELOCATE TAXI GUIDANCE SIGN PANEL	EACH	8	
AR901510	SEEDING	ACRE	35	
AR908513	MULCHING - METHOD 3	ACRE	35	
AR908520	EXCELSIOR BLANKET	S.Y.	1,500	

BASE BID NOTE:

THE BASE BID INCLUDES:

TAXIWAY P : STA. 627+15 TO STA. 635+75.
 RUNWAY 5-23 : STA. 33+25 TO STA. 42+25.
 RELOCATED TAXIWAY E : STA. 851+85 TO STA. 857+20.
 RELOCATED TAXIWAY D : STA. 858+20 TO STA. 863+65.
 EXISTING TAXIWAY E : STA. 880+00 TO STA. 885+00.