

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE				
20200100	EARTH EXCAVATION	CU YD	38	38				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	15	15				
25200110	SODDING, SALT TOLERANT	SO YD	15	15				
25200200	SUPPLEMENTAL WATERING	UNIT	1	1				
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	37037	37037				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	124	124				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	704	704				
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	1108	1108				
40604172	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N70	TON	5794	5794				
42001300	PROTECTIVE COAT	SO YD	1027	1027				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	3225	3225				
42400800	DETECTABLE WARNINGS	SO FT	220	220				
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	82159	82159				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0005 80% FED 20% STATE				
44000600	SIDEWALK REMOVAL	SO FT	3225	3225				
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	950	950				
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	800	800				
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	650	650				
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SO YD	48	48				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	147	147				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2				
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1				
63200310	GUARDRAIL REMOVAL	FOOT	50	50				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	38	38				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3				

REV. 4/15/2020 SEP
 * = SPECIALTY ITEMS
 Δ = NON-PARTICIPATING WORK (100% STATE)