

URBAN

URBAN

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT		0005	0014	0005
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	530		530	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	590		590	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	70		70	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	74		74	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	700	700		
21101605	TOPSOIL FURNISH AND PLACE, 2"	SQ YD	4,663		4663	
25000210	SEEDING, CLASS 2A	ACRE	5		5	
X2501800	SEEDING, CLASS 4 (MODIFIED)	ACRE	30		30	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	990		990	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	990		990	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	990		990	
25000750	MOWING	ACRE	35		35	
25003210	INTERSEEDING, CLASS 2A	ACRE	5		5	
25100115	MULCH, METHOD 2	ACRE	3		3	
25100630	EROSION CONTROL BLANKET	SQ YD	350		350	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300		300	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	30,298	30298		
40600300	AGGREGATE (PRIME COAT)	TON	510	510		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	39	39		
40600895	CONSTRUCT ^{ING} TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	204	204		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	317	317		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	5,346	5346		
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	12,688	12688		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	13,397	12688	709	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,808	3,808		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	5,332	5,332		
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	152,144	152144		
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1,371	1,371		
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	20	20		
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	20	20		
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	20	20		
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	25	25		
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	20	20		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	56	56		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	187	187		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,068	1068		
50102400	CONCRETE REMOVAL	CU YD	14	14		
50104650	SLOPEWALL REMOVAL	SQ YD	712	712		

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT		0005	0014	0005
50157300	PROTECTIVE SHIELD	SQ YD	2197		2197	
50300225	CONCRETE STRUCTURES	CU YD	2		2	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	11		11	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	730		730	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,844		2844	
50800515	BAR SPLICERS	EACH	28		28	
51100100	SLOPEWALL 4 INCH	SQ YD	579		579	
51100300	SLOPEWALL 6 INCH	SQ YD	133		133	
52100520	ANCHOR BOLTS, 1"	EACH	8		8	
58700300	CONCRETE SEALER	SQ FT	25,701		25701	
59000200	EPOXY CRACK INJECTION	FOOT	416		416	
64200105	SHOULDER RUMBLE STRIPS	FOOT	53,147	53147		
67100100	MOBILIZATION	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	30	30		
70300240	TEMPORARY PAVEMENT MARKING- LINE 6"	FOOT	9,251	9251		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	350	350	▲	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	7,663	7663		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	14,100	14100		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	42	42		
* 72000200	SIGN PANEL - TYPE 2	SQ FT	750	750		
* 72000300	SIGN PANEL - TYPE 3	SQ FT	3,619	3,619		
* 72400100	REMOVE SIGN PANEL ASSEMBLY- TYPE A	EACH	5	5		
* 72400200	REMOVE SIGN PANEL ASSEMBLY- TYPE B	EACH	27	27		
* 72400310	REMOVE SIGN PANEL- TYPE 1	SQ FT	42	42		
* 72400320	REMOVE SIGN PANEL- TYPE 2	SQ FT	307	307		
* 72400330	REMOVE SIGN PANEL- TYPE 3	SQ FT	3,684	3,684		
* 72600100	MILE POST MARKER ASSEMBLY	EACH	11	11		
* 72900200	METAL POST - TYPE B	FOOT	539	539		
* 73000100	WOOD SIGN SUPPORT	FOOT	750	750		
* 73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	31	31		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	66,136	66136		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	10,025	10025		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,761	1761		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	32	32		
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID- LINE 5"	FOOT	7,599	7599		
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID- LINE 8"	FOOT	829	829		
* 78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	1000	1000	▲	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I- LINE 4"	FOOT	7,762	7762		
* 78008220	POLYUREA PAVEMENT MARKING TYPE I- LINE 5"	FOOT	997	997		

Rev. 3-1-11

* SPECIALTY ITEMS

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE - 1/20/2011	REVISED -



STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: 1"=50' SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99(4&4-DRS-3	WILL	203	3
CONTRACT NO.			60M66	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				