

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				6-00548-0000	6-00548-0200	6-00548-0100
				ROADWAY	SHOULDER	STRUCTURE
				0005	0005	0013
				80% FED / 20 % ST	80% FED / 20 % ST	90% FED / 10 % ST
X7010200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 (SPECIAL)	EACH	1			1
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	2			2
X7200053	REMOVE, STORE AND RE-ERECT SIGN PANEL (SPECIAL)	EACH	10			10
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	1540			1540
Z0012164	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	1540			1540
Z0012162	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	1540			1540
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	63			63
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.6	0.1	0.3
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	22,8			22,8
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	25829	25829		
Z0034105	MATERIAL TRANSFER DEVICE	TON	6836	6836		
Z0049799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	8	8		
	DRAINAGE SCUPPER TO BE ADJUSTED	EACH	2			2
X4200003	COLD CENTRAL PLANT RECYCLING, 6 1/2"	SQ YD	19040		19040	
Ø Z0076600	TRAINEES	HOUR	2000	2000		
X4200004	CCPR EMULSIFIED ASPHALT	GALLON	53888		53888	
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	2000	2000		

Ø 0042

△ REV. 4-2-2020

REV. - MS

MODEL - Summary of Quantities
FILE NAME - pw:\blairroom\dc\illinois.gov\p\DOT\Documents\DOT - Offices\District 6\Projects\0672E00\CAD\Drawings\CAD\Sheet\72E00-sht.sou.dgn

USER NAME = TANJO	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 1/31/2020	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET 6 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	*	LOGAN	94	8
CONTRACT NO. 72E00			ILLINOIS FED. AID PROJECT	

(116)RS-6(117)RS-9(54-10)BDR-1