



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 9, 2020

SUBJECT: FAI Routes 57 & 74 (I-55 & I-74)  
Project NHPP-W12X(328)  
Section (10-34HB-3)BR & 10-5-1HB)BR-1  
Champaign County  
Contract No. 70B38  
Item No. 134, April 24, 2020 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Revised page 16 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

## TABLE OF CONTENTS

LOCATION OF PROJECT .....	1
DESCRIPTION OF PROJECT .....	1
TRAFFIC CONTROL PLAN .....	2
TRAFFIC CONTROL AND PROTECTION (SPECIAL) (EACH) .....	7
LIQUIDATED DAMAGES FOR NIGHTTIME CLOSURES.....	8
TRAFFIC CONTROL AND PROTECTION, (SPECIAL) (L SUM) .....	9
TEMPORARY CONCRETE BARRIER.....	10
TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 AND 701321.....	11
COOPERATION BETWEEN CONTRACTORS.....	12
CONTRACTOR ACCESS .....	12
DETOUR SIGNING.....	13
DIRECTION INDICATOR BARRICADES AND ARROW BOARDS .....	13
EQUIPMENT PARKING AND STORAGE .....	13
WIDTH RESTRICTION AND MAXIMUM WIDTH SIGNING .....	14
NOTIFICATION PRIOR TO ROAD CLOSURES .....	15
TEMPORARY TRAFFIC CONTROL DEVICE DEPLOYMENT AND REMOVAL .....	16
TEMPORARY TRAFFIC SIGNAL INSTALLATION .....	17
MODIFY EXISTING TRAFFIC SIGNAL TIMING FOR STAGE CONSTRUCTION .....	18
TRAFFIC CONTROL REMOVAL .....	18
BASE COURSE (OPTION) .....	19
BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN AND BLACK ANODIZED ALUMINUM SKIRT .....	20
BRIDGE DECK POUR WEATHER RESTRICTIONS .....	20
BRIDGE INSTRUMENTATION .....	21
CAMERA POLE, 45 FT.....	28
CCTV CAMERA.....	28
CLOSED CIRCUIT TELEVISION CABINET.....	29
CONSTRUCTION LAYOUT EQUIPMENT .....	29
DETECTOR LOOP, TYPE 1 .....	30
DRAINAGE STRUCTURE TO BE REMOVED .....	30
DRILL EXISTING HANDHOLE .....	30

Revised April 9, 2020

**TEMPORARY TRAFFIC CONTROL DEVICE DEPLOYMENT AND REMOVAL**

Effective: January 01, 2014

If the contractor's operations require them to have lane closures in either the driving or passing lanes, the Contractor shall deploy and pick up their traffic control devices (drums, barricades, etc.) from the closed lane side. Dragging devices across the open lanes of traffic will not be allowed. Failure to comply with this Special Provision will result in a traffic control deficiency deduction being assessed as specified in Article 105.03(b) of the Standard Specifications.

Revised April 9, 2020