

FILE PATH = p:\AECOM\NA\MSI\ecocom\lme\local\AECOM_DS02_NA\Documents\01_Americas\Transportation\6269938_Circle\Phase_1\1000_CAD\005_Roadway\Sheets\62A77_Contract\1162A77-SHT-500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FED 10% STATE ROADWAY	100% STATE ROADWAY	90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING		
				0004 URBAN	0004 URBAN	0005 URBAN	0010 016-D006	0044 016-1823	0044 016-1164	0044 016-1189	0021 URBAN		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,168	1,168									
20101000	TEMPORARY FENCE	FOOT	120	120									
20101100	TREE TRUNK PROTECTION	EACH	8	8									
20200100	EARTH EXCAVATION	CU YD	31,330	31,330									
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	8,306	8,306									
20700220	POROUS GRANULAR EMBANKMENT	CU YD	2,116	2,116									
20800150	TRENCH BACKFILL	CU YD	8,216	8,216									
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	17,248	17,248									
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	16,314	16,314									
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	100	100									
21301084	EXPLORATION TRENCH 84" DEPTH	FOOT	100	100									
* 25000210	SEEDING, CLASS 2A	ACRE	3.75	3.75									
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	339	339									
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	339	339									



* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM % 0042

REV. 4-13-2020 REV-SEP



0162A77-SHT-500
 USER NAME = PIMSARNO
 PLOT SCALE = 2.0000' / 1" =
 PLOT DATE = 1/31/2020

DESIGNED - ZND REVISED -
 DRAWN - ZND REVISED -
 CHECKED - MJJ REVISED -
 DATE - 1/29/2019 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 29 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2015-018R	COOK	1360	5
CONTRACT NO. 62A77				
ILLINOIS FED. AID PROJECT				

FILE PATH = p:\a\ecdm\ms-ansi\ecdm\local\ecdm\0502_MN\Documents\01_Americas\Transportation\6269938 Circle Phase 1\000_CAD\005_Roadway\Sheets\62A77_Contract\1162A77-SHT-500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				90% FED 10% STATE ROADWAY	100% STATE ROADWAY	90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING			
				0004 URBAN	0004 URBAN	0005 URBAN	0010 016-D006	0044 016-1823	0044 016-1164	0044 016-1189	0021 URBAN			
25100115	MULCH, METHOD 2	ACRE	12	12										
* 25100630	EROSION CONTROL BLANKET	SQ YD	16,314	16,314										
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,200	1,200										
28000400	PERIMETER EROSION BARRIER	FOOT	7,715	7,715										
28000510	INLET FILTERS	EACH	306	306										
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	4,726	4,726										
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	57,098	56,911			187							
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	5,140	5,140										
31101600	SUBBASE GRANULAR MATERIAL, TYPE B 8"	SQ YD	2,399	2,399										
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	46,403	46,403										
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	250	250										
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	24,450	400			24,050							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	85				85							
40602985	HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70	TON	516				516							

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM % 0042 REV. 4-13-2020 REV-SEP



0162A77-SHT-500
 USER NAME = PIMSARNO
 PLOT SCALE = 2.0000' / 1" =
 PLOT DATE = 1/31/2020

DESIGNED - ZND	REVISED -
DRAWN - ZND	REVISED -
CHECKED - MJJ	REVISED -
DATE - 1/29/2019	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: SHEET 2 OF 29 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2015-018R	COUNTY COOK	TOTAL SHEETS 1360	SHEET NO. 6
CONTRACT NO. 62A77				
ILLINOIS FED. AID PROJECT				

FILE PATH = p:\AECOM\NA\MSI\ecocom\local\AECOM_0502_NA\Documents\01_Americas\Transportation\6269938_Circle\Phase_1\1000_CAD\005_Roadway\Sheets\62A77_Contract\1162A77-SHT-500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FED 10% STATE ROADWAY	100% STATE ROADWAY	90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING		
				0004 URBAN	0004 URBAN	0005 URBAN	0010 016-D006	0044 016-1823	0044 016-1164	0044 016-1189	0021 URBAN		
48300710	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/2"	SQ YD	3,754	3,754									
50102400	CONCRETE REMOVAL	CU YD	201					201					
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2									
50200100	STRUCTURE EXCAVATION	CU YD	898					898					
50300225	CONCRETE STRUCTURES	CU YD	57.0				44.8	12.2					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	244.7				100	144.7					
50300300	PROTECTIVE COAT	SQ YD	647				228	419					
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	32.3					32.3					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	106,790				59,920	46,870					
50800515	BAR SPLICERS	EACH	250				250						
50901720	BICYCLE RAILING	FOOT	361						361				
51100100	SLOPE WALL 4 INCH	SQ YD	315	315									
51500100	NAME PLATES	EACH	2				1	1					
52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,563	1,563									
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	691	691									

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

0042

REV. 4-13-2020

REV-SEP



0162A77-SHT-500
 USER NAME = PIMSARNQ
 PLOT SCALE = 2.0000' / 1" =
 PLOT DATE = 1/31/2020

DESIGNED - ZND
 DRAWN - ZND
 CHECKED - MJJ
 DATE - 1/29/2019

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 5 OF 29 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2015-018R	COOK	1360	9
CONTRACT NO. 62A77			ILLINOIS FED. AID PROJECT	

FILE PATH = p:\aecom\ms-ansi\ecomm\local\ecomm\0502_NA\Documents\01_Americas\Transportation\6269938 Circle Phase II\000_CAD\005_Roadway\Sheets\62A77_Contract\0162A77-SHT-500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				90% FED 10% STATE ROADWAY	100% STATE ROADWAY	90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING			
				0004 URBAN	0004 URBAN	0005 URBAN	0010 016-D006	0044 016-1823	0044 016-1164	0044 016-1189	0021 URBAN			
55101200	STORM SEWER REMOVAL 24"	FOOT	511	511										
55101400	STORM SEWER REMOVAL 30"	FOOT	164	164										
55101900	STORM SEWER REMOVAL 48"	FOOT	186	186										
55102100	STORM SEWER REMOVAL 60"	FOOT	63	63										
55201000	STORM SEWERS JACKED IN PLACE, 27"	FOOT	273	273										
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1	1										
58700300	CONCRETE SEALER	SQ FT	8,756					2,035	6,307	414				
59000200	EPOXY CRACK INJECTION	FOOT	143					79	46	18				
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	118	118										
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	16	16										
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	600	600										
60108206	PIPE UNDERDRAINS, TYPE 2, 6"	FOOT	14,137	14,137										
60200105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	5	5										
60200905	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 9 FRAME AND GRATE	EACH	4	4										

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

% 0042

△ REV. 4-13-2020

REV-SEP



0162A77-SHT-500
 USER NAME = PIMSARNO
 PLOT SCALE = 2.0000' / in.
 PLOT DATE = 1/31/2020

DESIGNED - ZND
 DRAWN - ZND
 CHECKED - MJJ
 DATE - 1/29/2019

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 7 OF 29 SHEETS STA. TO STA.

F.A.I. RTE. 90/94/290	SECTION 2015-018R	COUNTY COOK	TOTAL SHEETS 1360	SHEET NO. 11
CONTRACT NO. 62A77				
ILLINOIS FED. AID PROJECT				

FILE PATH = p:\AECOM\NA\ANSI\escomon\lms\local\AECOM_0502_NA\Documents\01_America\Transportation\62629338_Circle\Phase 1\000_CAD\006_Roadway\Sheets\62A77_Contract\1162A77-SHT-500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FED 10% STATE ROADWAY	100% STATE ROADWAY	90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING		
				0004 URBAN	0004 URBAN	0005 URBAN	0010 016-D006	0044 016-1823	0044 016-1164	0044 016-1189	0021 URBAN		
60201310	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 20 FRAME AND GRATE	EACH	107	107									
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	1	1									
60207005	CATCH BASINS, TYPE C, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	6	6									
60207805	CATCH BASINS, TYPE C, TYPE 10 FRAME AND GRATE	EACH	5	5									
60208210	CATCH BASINS, TYPE C, TYPE 20 FRAME AND GRATE	EACH	4	4									
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	40	40									
60219000	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 8 GRATE	EACH	1	1									
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5									
60223800	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6									
60224446	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4									
60224469	MANHOLES, TYPE A, 9' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2									
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	27	27									
60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	1	1									
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	34	34									

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

% 0042

REV. 4-13-2020

REV-SEP



0162A77-SHT-500
 USER NAME = PIMSARNO
 PLOT SCALE = 2.0000' / in.
 PLOT DATE = 1/31/2020

DESIGNED - ZND
 DRAWN - ZND
 CHECKED - MJE
 DATE - 1/29/2019

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 8 OF 29 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2015-018R	COOK	1360	12
CONTRACT NO. 62A77				
ILLINOIS FED. AID PROJECT				

FILE PATH = p:\AECOM\NA\MSI\ecommon\local\AECOM_DS02_NA\Documents\01_Americas\Transportation\6269938_Circle\Phase_1\1000_CAD\005_Roadway\Sheets\62A77_Contract\1162A77-SHT-500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				90% FED 10% STATE ROADWAY	100% STATE ROADWAY	90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING			
				0004 URBAN	0004 URBAN	0005 URBAN	0010 016-D006	0044 016-1823	0044 016-1164	0044 016-1189	0021 URBAN			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6,801	6,801										
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	7,046	7,046										
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	259	259										
* 78004350	PERFORMED PLASTIC PAVEMENT MARKING, TYPE D - INLAID - LETTERS AND SYMBOLS	SQ FT	1,654	1,654										
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	24,840	24,840										
* 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	21,195	21,195										
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	1,564	1,564										
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,523	1,523										
* 78100300	REPLACEMENT REFLECTOR	EACH	372	372										
* 78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	6,287	6,287										
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	772	772										
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	3,353										3,353	
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	305										305	
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	20										20	
* 81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	800										800	

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM % 0042

△ REV. 4-13-2020

REV-SEP



0162A77-SHT-500
 USER NAME = PIMSARNO
 PLOT SCALE = 2.0000' / 1" =
 PLOT DATE = 1/31/2020

DESIGNED - ZND REVISED -
 DRAWN - ZND REVISED -
 CHECKED - MJJE REVISED -
 DATE - 1/29/2019 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 14 OF 29 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2015-018R	COOK	1360	18
ILLINOIS FED. AID PROJECT			CONTRACT NO. 62A77	

FILE PATH = p:\AECOM\NA-AWSI\ecommon\local\AECOM_DS02_NA\Documents\01_Americas\Transportation\6269938_Circle\Phase_1\000_CAD\005_Roadway\Sheets\62A77_Contract\1162A77-SHT-500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				90% FED 10% STATE ROADWAY	100% STATE ROADWAY	90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING							
				0004 URBAN	0004 URBAN	0005 URBAN	0010 016-D006	0044 016-1823	0044 016-1164	0044 016-1189	0021 URBAN							
* 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	155															155
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	20															20
* 81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	1,360															1,360
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	3															3
* 81300830	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 8"	EACH	6															6
* 81301500	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 28" X 12" X 6"	EACH	1															1
* 81400200	HEAVY-DUTY HANDHOLE	EACH	9															9
* 81603081	UNIT DUCT, 600V, 3-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	3,731															3,731
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	40															40
* 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	161															161
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	2,399															2,399
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	910															910
* 81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	2,730															2,730
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	2,742															2,742

9



* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM % 0042

REV. 4-13-2020

REV-SEP



0162A77-SHT-500
 USER NAME = PIMSARNO
 PLOT SCALE = 2,0000' / in.
 PLOT DATE = 1/31/2020

DESIGNED - ZND REVISED -
 DRAWN - ZND REVISED -
 CHECKED - MJJ REVISED -
 DATE - 1/29/2019 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: SHEET 15 OF 29 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2015-018R	COOK	1360	19
CONTRACT NO. 62A77				
ILLINOIS FED. AID PROJECT				

FILE PATH = p:\aecom\ms-ansi\ecommon\local\ecom\0502_NA\Documents\01_Americas\Transportation\6269938_Circle\Phase\1\000_CAD\006_Roadway\Sheets\62A77_Contract\0162A77-SHT-500

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FED 10% STATE ROADWAY	100% STATE ROADWAY	90% FED 10% STATE ROADWAY	90% FED 10% STATE BRIDGE	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE RETAINING WALL	90% FED 10% STATE HIGHWAY LIGHTING		
				0004 URBAN	0004 URBAN	0005 URBAN	0010 016-D006	0044 016-1823	0044 016-1164	0044 016-1189	0021 URBAN		
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	15,048			15,048							
X7030035	WET REFLECTIVE TEMPORARY TAPE TYPE III, 5 INCH	FOOT	4,887			4,887							
X7035100	TEMPORARY EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	423	207		216							
X7035104	TEMPORARY EPOXY PAVEMENT MARKING - LINE 4"	FOOT	105,754	97,610		8,144							
X7035105	TEMPORARY EPOXY PAVEMENT MARKING - LINE 5"	FOOT	18,878	15,508		3,370							
X7035108	TEMPORARY EPOXY PAVEMENT MARKING - LINE 8"	FOOT	53,778	45,606		8,172							
X7035112	TEMPORARY EPOXY PAVEMENT MARKING - LINE 12"	FOOT	3,489	3,489									
X7040125	PINNING TEMPORARY CONCRETE BARRIER	EACH	6,838	6,838									
X7200053	REMOVE, STORE AND RE-ERECT SIGN PANEL (SPECIAL)	EACH	5	5									
X7333095	OVERHEAD SIGN STRUCTURE - SPAN (SPECIAL)	FOOT	196	196									
X7333105	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED (SPECIAL)	FOOT	53	53									
X7830060	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	4,561	4,561									
X7830050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	500	500									
* X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	2,774	2,774									
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	13,499	13,499									

8,172



* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

% 0042

REV. 4-13-2020

REV-SEP



0162A77-SHT-500
 USER NAME = PIMSARNO
 PLOT SCALE = 2.0000' / in.
 PLOT DATE = 1/31/2020

DESIGNED - ZND
 DRAWN - ZND
 CHECKED - MJE
 DATE - 1/29/2019

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 26 OF 29 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2015-018R	COOK	1360	30
CONTRACT NO. 62A77			ILLINOIS FED. AID PROJECT	