

# SUMMARY OF QUANTITIES

SPECIALTY ITEM	SPECIAL PROVISIONS	CODE NUMBER	ITEM	UNIT OF MEASURE	QUANTITY	Construction Code 0028 Federal 80%/Local 20%
	X	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	3,130	3,130
	X	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	505	505
		20101000	TEMPORARY FENCE	FOOT	445	445
*		20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	150	150
	X	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	310	310
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	930	930
	X	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	6,200	6,200
*		25000115	SEEDING, CLASS 1B	ACRE	0.50	0.50
*		25000200	SEEDING, CLASS 2	ACRE	0.50	0.50
*		25000312	SEEDING, CLASS 4A	ACRE	4.00	4.00
*		25000314	SEEDING, CLASS 4B	ACRE	0.50	0.50
*		25100630	EROSION CONTROL BLANKET	SQ YD	25,250	25,250
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	550	550
		28000400	PERIMETER EROSION BARRIER	FOOT	1,200	1,200
		28000500	INLET AND PIPE PROTECTION	EACH	6	6
		28100105	STONE RIPRAP, CLASS A3	SQ YD	16	16
		28100107	STONE RIPRAP, CLASS A4	SQ YD	112	112
		28200200	FILTER FABRIC	SQ YD	128	128
	X	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	930	930
		35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	5,295	5,295
		40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	8,080	8,080
	X	40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	690	690
	X	44000100	PAVEMENT REMOVAL	SQ YD	1,690	1,690
		50200100	STRUCTURE EXCAVATION	CU YD	59	59
		50300225	CONCRETE STRUCTURES	CU YD	22	22
		50300300	PROTECTIVE COAT	SQ YD	415	415
		50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	29	29
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9,950	9,950
		51100300	SLOPE WALL 6 INCH	SQ YD	21	21
		51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	240	240
		51202305	DRIVING PILES	FOOT	240	240
		51203200	TEST PILE METAL SHELLS	EACH	2	2
		54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2
		55000050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	282	282

SPECIALTY ITEM	SPECIAL PROVISIONS	CODE NUMBER	ITEM	UNIT OF MEASURE	QUANTITY	Construction Code 0028 Federal 80%/Local 20%
		55000050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	14	14
		58800101	GRANULAR BACKFILL FOR STRUCTURES	CUYD	56	56
		58700300	CONCRETE SEALER	SQ FT	118	118
		59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	63	63
		60100050	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4	4
		60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1
		60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	3	3
		60220200	MANHOLES, TYPE A, 4'-DIAMETER	EACH	1	1
		60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1
*		66400205	CHAIN LINK FENCE, 5'	FOOT	650	650
*		66701001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1
*		66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	530	530
*		66901006	REGULATED SUBSTANCES MONITORING	CAL DAY	6	6
*		66903530	SOIL DISPOSAL ANALYSIS	EACH	2	2
*		66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1
		67100100	MOBILIZATION	L SUM	1	1
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	LSUM	1	1
		70102840	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	LSUM	1	1
*		72000100	SIGN PANEL - TYPE 1	SQFT	24	24
*		72800100	METAL POST - TYPE A	FOOT	80	80
*		78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,660	3,660
*		78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	10	10
	X	Z0004002	BOLLARDS	EACH	2	2
	X	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	232	232
	X	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	171	171
#	X	Z0076604	TRAINEES	HOURS	1000	1000
#	X	Z0076604	TRAINEES TPG	HOURS	1000	1000
*	X	Z0077900	WOOD POST AND RAIL FENCE	FOOT	40	40
	X	X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1
	X	X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	2410	2410
	X	X0325110	BIAXIAL GEOGRID	SQ YD	930	930
	X	X0350805	FOLD DOWN BOLLARDS	EACH	1	1
	X	X2020410	EARTH EXCAVATION, SPECIAL	CU YD	2,300	2,300
	X	X5091730	BRIDGE FENCE RAILING SPECIAL	FOOT	400	400
	X	X8640302	CHAIN LINK FENCE REMOVAL (Special)	FOOT	365	365
	X	XX008287	BOARDWALK STRUCTURE	SQ FT	1320	1320
	X	XX009348	TIMBER STRINGER RECREATION BRIDGE, LOCATION 1	SQ FT	416	416
	X	XX009349	TIMBER STRINGER RECREATION BRIDGE, LOCATION 2	SQ FT	240	240

# 0042

\\192.168.1.105\H\_drive\Systems\Perkins\160910.00 GreatWesternTram\Extention\160910.P2 Phase II Engineering\CAD\160910.P2 General Notes & Details.dwg Updated by: skustusch 3/17/2020



USER NAME = skustusch	DESIGNED - AK	REVISED - 4-11/31/20
PLOT SCALE = *SCALE*	DRAWN - RT	REVISED - ---
PLOT DATE = 3/17/2020	CHECKED - JM	REVISED - ---
	DATE - 11/08/19	REVISED - ---

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	18-P4006-01-BT	DEKALB	53	3
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 87730	