ROUTE: IL 47 NEAR WOODSTOCK

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PVT MKS
ROUTE 14	ROUTE 176 (E)	SB	1	6	20	120	13	13						
ROUTE 14	ROUTE 176 (E)	SB	1	2	300	600	67	67						
ROUTE 14	ROUTE 176 (E)	SB	1	2	20	40	4		4					
1.6 MILES LUCAS ROAD		SB	1	2	15	30	3	3						
1.8 MILES LUCAS ROAD		SB	1	2	6	12	1	1						
2.3 MILES LUCAS ROAD		SB	1	2	12	24	3	3						
2.4 MILES LUCAS ROAD		SB	1	3	12	36	4		4					
3.3 MILES LUCAS ROAD		SB	1	6	13	78	9	9						
ROUTE 176 (E)	ROUTE 14	NB	1											
0.4 MILES		NB	1	6	30	180	20				20			
			1	13	100	1300	144	144						
			1	2	40	80	9			9				
			1	2	2	4	1		1					
			1	2	2	4	1		1					
ROUTE 62	ROUTE 176 (E)	NB												
2.1 MILE NORTH		NB	1	2	2	4	1		1					
2.1 MILE NORTH		NB	1	2	2	4	1		1					
2.1 MILE NORTH		NB	1	2	2	4	1		1					
2.9 MILE NORTH		NB	1	6	100	600	67	67						
2.9 MILE NORTH		NB	1	3	50	150	17	17						
2.9 MILE NORTH		NB	1	3	20	60	7	7						
3.8 MILE NORTH		NB	1	8	13	104	12			12				
3.8 MILE NORTH		NB	1	3	3	6	1		1					
3.9 MILE NORTH		NB	1	2	2	4	1		1					
3.9 MILE NORTH		NB	1	3	300	900	100	100						
4.1 MILE NORTH		NB	1	10	13	130	14			14				
4.1 MILE NORTH		NB	1	10	13	130	14			14				
4.1 MILE NORTH		NB	1	6	6	36	4			4				
4.1 MILE NORTH		NB	1	6	6	36	4			4				
4.2 MILE BALLARD ROAD		NB	1	13	300	3900	433	433						
4.2 MILE BALLARD ROAD		NB	1	13	20	260	29			29				
4.2 MILE BALLARD ROAD		NB	1	6	6	36	4			4				
4.2 MILE BALLARD ROAD		NB	1	3	15	45	5	5						
4.4 MILE BALLARD ROAD		NB	1	13	300	3900	433	433						
ROUTE 176 (E)	ROUTE 62	SB	1	8	13	104	12	12						
ROUTE 176 (E)	ROUTE 62	SB	1	6	15	90	10			10				
0.4 MILE SOUTH		SB	1	13	300	3900	433	433						
0.4 MILE SOUTH		SB	1	3	3	9	1		1					
0.4 MILE SOUTH		SB	1	3	20	60	7			7				
0.9 MILE SOUTH		SB	1	10	13	130	14			14				
2.1 MILES SOUTH		SB	1	8	13	104	12			12				
2.3 MILES SOUTH		SB	1	3	13	39	4	4						
2.4 MILES SOUTH		SB	1	2	300	600	67	67						
2.4 MILES SOUTH		SB	1	2	13	26	3	3						
2.4 MILES SOUTH		SB	1	2	13	26	3	3						
LAKE AVE	MCCONNELL	NB/SB	1	36	500	18000	2000	2000						
		TOTALS:					3993 SY	3824 SY	16 SY	134 SY	20 SY		FT	EACH

FILE NAME = c:\projects\d136108\design_ea.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/14/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 47

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-010 PP	MCHENRY	27	13
		CONTRACT NO. 60E36		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT