

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT			1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15					
40600300	AGGREGATE (PRIME COAT)	TON	72	72					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35	35					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1210	1210					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1752	1752					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1180	1180					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2985	2985					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	28704	28704					
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SO YD	6804	6804					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	7025	7025					
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SO YD	42	42					
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SO YD	15	15					
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SO YD	80	80					
44201761	CLASS B PATCHES, TYPE I, 10 INCH	SO YD	1262	1262					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	4904	4904					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	847	847					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	634	634					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21076	21076					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500	500					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	740	740					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	740	740					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	1748	1748					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT			1000-2A				
X0324626	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/4"	SO YD	176	176					
* XX006058	POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	700	700					

* SPECIALTY ITEM

Rev. 4-21-08

(4-9-08)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLDT DATE: 4/9/2008

WILL COUNTY ROUTE SEGMENT	HMA SURF REM 2-1/4" & RESURF (SY)	HMA SURF REM (SP) & RESURF (SY)	CLASS D PATCH TYPE I (SY)	CLASS D PATCH TYPE II (SY)	CLASS D PATCH TYPE III (SY)	CLASS D PATCH TYPE IV (SY)	PAVT MARKING 4" (FT)	PAVT MARKING 6" (FT)	RAISED REFL PAVT MKS (EACH)
CENTER STREET (MCDONOUGH ST TO BRANDON RD)	656	0		10			220		12
CHICAGO ROAD (MISSISSIPPI TO HOFF ROAD)	0	0		15			10		4
CHICAGO ROAD (NORTH OF IL 102)	0	2000		694			100		10
COAL CITY ROAD (IL 113 TO IL 53)	395	0		39			400		20
GOVERNORS HIGHWAY (UNIVERSITY PARKWAY TO IL 50)	961	0		26			1582		16
HOFF ROAD (WEST OF CHICAGO ROAD TO 7.37 MILE EAST)	0	0		120			20		10
IL 50 / CICERO AVENUE (GOVERNORS HWY TO COUNTY LINE ROAD)	607	1247		130	128	53	3834		38
IL 53 (RIVER ROAD TO DIVISION STREET)	0	512		62			550		30
IL 102 (COUNTY LINE TO IL 53)	933	0		123	41		350		20
IL 102 (COUNTY LINE TO IL 53)	5774	0		342		67	1210		60
IL 113 (0.5 MILE EAST OF HORSE CREEK TO COUNTY LINE)	0	0		98			40		10
IL 113 (DIVISION STREET TO GRUNDY COUNTY LINE)	7658	0		0			1550		80
IL 113 (IL 129 TO CUSTER PARK FIREHOUSE)	133	0		497			100		20
IL 113 (MAIN STREET TO COAL CITY ROAD)	107	0		18		33	60		6
IL 129 (I-55 TO COAL CITY ROAD)	0	0		17			20		6
IL 129 (IL 113 TO COUNTY LINE)	0	0		904	352	67	60		4
MANHATTAN MONEE (SCHEER ROAD TO CEDAR ROAD)	1062	0		36	61	113	1950		43
RICHARDS STREET (4TH ST TO US 52)	0	0		266			20		12
US 45 (STUENKEL ROAD TO 179TH STREET)	0	18		79	20		100		10
US 52 (DELANEY ROAD TO BAKER ROAD)	4271	0		27			2530		59
US 52 (300 FT E/O MCDONALD ROAD TO AIRPORT ROAD)	448	33		32	32		140		12
US 52 (WILTON CENTER TO US 45)	134	0		116	68	173	160		10
US 6 (200 FT E/O HOUBOLT RD TO EMPRESS DR)	1920	0		27			2880	500	28
US 6 (WALNUT ST TO BRIGGS ST)	159	0		31	17		400		8
US 30 (80TH AVENUE TO SCHOOLHOUSE ROAD)	978	0		235			660		40
US 30 (CEDAR ROAD TO GOUGER ROAD)	0	2650		278			150		10
US 30 (SCHOOLHOUSE ROAD TO SPENCER ROAD)	0	0		340		66	50		10
US 30 (WASHINGTON ST TO US 6)	0	0		84	66		20		6
WASHINGTON STREET (US 30 TO BRIGGS ROAD)	0	0		39			10		6
IL 1 (STEGER ROAD TO COUNTY LINE ROAD)	2508	350		219	62	62	1800		100
SUMMARY TOTALS:	28704	6804	0	4904	847	634	21076	500	700

NOTE:

ALL MILLING AREAS AS NOTED ON THE INDIVIDUAL PATCHING SCHEDULES WITH A PATCH WIDTH OF 3 FEET OR LESS AND PATCH LENGTH OF 25 FEET OR MORE SHALL BE PAID FOR AS HOT-MIX ASPHALT SURFACE REMOVAL (SPECIAL).

ALL CLASS D, TYPE I PATCHES SHOWN ON THE PATCHING SCHEDULES SHALL BE ADJUSTED IN THE FIELD BY THE ENGINEER TO CLASS D, TYPE II PATCHES.

WILL COUNTY ROUTE SEGMENT (PCC SECTIONS)	PCC SURF REM 2-1/4" RESURF (SY)	HMA SURF REM (SP) & RESURF (SY)	CLASS C PATCH TYPE I (SY)	CLASS C PATCH TYPE II (SY)	CLASS C PATCH TYPE III (SY)	CLASS C PATCH TYPE IV (SY)	PAVT MARKING 4" (FT)	RAISED REFL PAVT MKS (EACH)
IL 50 (STEGER ROAD TO GOVERNORS HIGHWAY)	176	0	42	15	80	0	700	40
SUMMARY TOTALS:	176	0	42	15	80	0	700	40

△ Rev. Sheet 4-21-08

(4-18-08)

FILE NAME: c:\projects\133388\design\as.dgn	USER NAME: wlgroendp	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF PATCHING SCHEDULE WILL COUNTY				F.A.P. RTE. VAR.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 1/8" = 1' / 31L	CHECKED: -	REVISED: -	REVISED: -		SCALE:	SHEET NO. OF	SHEETS	STA.	TO STA.	2008-012 PP	WILL	33	5
PLOT DATE = 4/18/2008	DATE: -	REVISED: -	REVISED: -						CONTRACT NO. 60E38				
									FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				