

### INDEX TO SHEETS

- 1.) COVER SHEET, LOCATION MAP
- 2.) INDEX OF SHEETS, INDEX OF STATE STANDARDS, SUMMARY OF QUANTITIES
- 3.) GENERAL NOTES, HOT-MIX ASPHALT MIXTURE REQUIREMENTS
- 4.) TYPICAL CROSS SECTIONS
- 5.-6.) PLAN: STATE ROAD (PAVING)
- 7.-8.) PLAN: STATE ROAD (PAVEMENT MARKING)
- 9.) DISTRICT ONE TYPICAL PAVEMENT MARKINGS
- 10.) PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
- 11.) TRAFFIC CONTROL AND PROTECTION FOR SIDEROADS, INTERSECTIONS, AND DRIVEWAYS
- 12.) SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
- 13.) CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
- 14.) DETAILS FOR FRAMES AND LIDS ADJUSTMENTS WITH MILLING
- 15.) BUTT JOINT AND HOT-MIX ASPHALT TAPER DETAILS
- 16.) PAVEMENT PATCHING FOR HOT-MIX ASPHALT SURFACED PAVEMENT

### STATE STANDARDS

- 000001-05 STANDARDS SYMBOLS, ABBREVIATIONS, AND PATTERNS
- 424001-05 CURB RAMPS FOR SIDEWALKS
- 442201-03 CLASS C AND D PATCHES
- 604001-02 FRAME & LIDS, TYPE 1
- 606001-03 CONCRETE CURB AND COMBINATION CONCRETE CURB & GUTTER
- 701501-04 URBAN LANE CLOSURE, 2 L, 2 W UNDIVIDED
- 701502-02 URBAN LANE CLOSURE, 2 L, 2 W BIDIRECTIONAL LEFT TURN LANE
- 701701-05 URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701801-03 LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 701901 TRAFFIC CONTROL DEVICES
- 780001-01 TYPICAL PAVEMENT MARKINGS
- 886001 DETECTOR LOOP INSTALLATIONS
- 886006 TYPICAL LAYOUTS FOR DETECTOR LOOPS

### SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	CONSTRUCTION CODE 1000-2A	QUANTITY
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD.		50
20700220	POROUS GRANULAR EMBANKMENT	CU. YD.		50
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD		1,840
35800100	PREPARATION OF BASE	SQ YD		50
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL.		3,178
40600300	AGGREGATE (PRIME COAT)	TON		34
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD		282
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON		5
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON		232
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON		308
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON		2,517
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON		9
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT		220
42400800	DETECTABLE WARNINGS	SQ FT		10
44000100	PAVEMENT REMOVAL	SQ YD		1,840
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD		31,781
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD		50
44000600	SIDEWALK REMOVAL	SQ FT		220
* 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT		636
44002204	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1"	SQ YD		87
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD		12
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD		25
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD		40
* 60249400	VALVE BOXES 6"	EACH		7
60250200	CATCH BASINS TO BE ADJUSTED	EACH		17
* 60266610	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH		6
* 60300305	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH		24
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH		10
67100100	MOBILIZATION	L SUM		1
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM		1
70106800	CHANGEABLE MESSAGE SIGN	CAL MON		3
70300100	SHORT TERM PAVEMENT MARKING	FOOT		1,625
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		1,634
70300220	TEMPORARY PAVEMENT MARKING - LINE, 4"	FOOT		32,450
70300240	TEMPORARY PAVEMENT MARKING - LINE, 6"	FOOT		11,660
70300260	TEMPORARY PAVEMENT MARKING - LINE, 12"	FOOT		740
70300280	TEMPORARY PAVEMENT MARKING - LINE, 24"	FOOT		1,292
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT		540
△ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		817
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE, 4"	FOOT		16,225
△ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE, 6"	FOOT		5,830
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE, 12"	FOOT		370
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE, 24"	FOOT		646
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT		1,280
* X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON		1,349

\* DENOTES SPECIAL PROVISION

△ DENOTES SPECIALITY ITEM



**Frank Novotny & Associates, Inc.**

Civil Engineers/ Municipal Consultants 825 Midway Drive ♦ Willowbrook, IL ♦ 60527 ♦ Telephone: (630) 887-8640 ♦ Fax: (630) 887-0132 Illinois Professional Design Firm No. 184-000928

PROJECT

CITY OF BURBANK, ILLINOIS  
STATE ROAD LAPP RESURFACING  
87th STREET to 79th STREET  
MFT SECTION NO. 06-00044-00-RS

R E V I S I O N S			
NO.	BY	DATE	DESCRIPTION
1	BAH	12/07	PER IDOT REVIEW
2	TPG	1/23/08	PER IDOT REVIEW

INDEX TO SHEETS  
STATE STANDARDS  
SUMMARY OF QUANTITIES

PROJECT NO. 05480	SCALE AS NOTED	SHEET 2 OF 16 SHEETS
DRAWN/DESIGNED JFP/TPG	DATE OCT., 2007	
CHECKED/APPROVED TPG	FIELD BOOK NO. FILE	