

			/007
CODE NUMBER	PAY ITEM	UNIT	100% STATE TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	60
20100500	TREE REMOVAL, ACRES	ACRE	0.4
20200100	EARTH EXCAVATION	CU YD	2711
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	252
20400800	FURNISHED EXCAVATION	CU YD	491
* 25000210	SEEDING, CLASS 2A	ACRE	1.25
* 25000310	SEEDING, CLASS 4	ACRE	0.25
* 25000750	MOWING	ACRE	1.5
* 25100115	MULCH, METHOD 2	ACRE	1.5
* 25100630	EROSION CONTROL BLANKET	SQ YD	4900
* 25100900	TURF REINFORCEMENT MAT	SQ YD	2400
28000300	TEMPORARY DITCH CHECKS	EACH	40
28000400	PERIMETER EROSION BARRIER	FOOT	300
28000500	INLET PIPE PROTECTION	EACH	1
28100105	STONE RIPRAP, CLASS A3	SQ YD	32.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	84
28200200	FILTER FABRIC	SQ YD	121
35101400	AGGREGATE BASE COURSE, TYPE B	TON	41
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	21.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	25.0
42001200	PAVEMENT FABRIC	SQ YD	300.0
44000400	GUTTER REMOVAL	FOOT	306.0
44002500	GUTTER OUTLET REMOVAL	EACH	2.0
44201421	CLASS C PATCHES, TYPE IV, 15 INCH	SQ YD	300.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	110.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
51901105	STEEL RAILING	FOOT	28.3
51500100	NAME PLATES	EACH	1
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1
54011008	CONCRETE PRECAST BOX CULVERT 10' X 8'	FOOT	140

• SPECIALTY ITEMS