

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
17	15T-2	CARROLL	71	14
STA. TO STA.				
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	

61101013 STORM SEWERS PROTECTED, CLASS A, 12"

FOOT	LOCATION
85	1239 + 75
85	TOTAL

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.

EACH	LOCATION	
1	1211 + 50	LT
1	1211 + 75	LT
2	1239 + 75	RT
1	1239 + 75	LT
1	1358 + 95	LT
6	TOTAL	

63100110 TRAFFIC BARRIER TERMINAL, TYPE II

EACH	LOCATION	
1	1240 + 10	LT
1	TOTAL	

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	
277	1210 + 27.00 - 1213 + 4	RT
290	1210 + 27.00 - 1213 + 17	LT
100.5	1239 + 12.50 - 1240 + 13	RT
100.5	1239 + 34.50 - 1240 + 35	LT
275	1357 + 67.00 - 1360 + 42	RT
276	1357 + 79.00 - 1360 + 55	RT
1319.0	TOTAL	

63300575 REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARDRAIL

FOOT	LOCATION	
55	1239 + 55 - 1240 + 10	LT
53	1239 + 60 - 1240 + 13	RT
108	TOTAL	

63500105 DELINEATORS

EACH	LOCATION	
2	1211 + 65.00	RT & LT
2	1240 + 74.00	RT & LT
2	1359 + 17.00	RT & LT
6	TOTAL	RT & LT

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION	
2	1210 + 00	RT & LT
2	1211 + 00	RT & LT
2	1211 + 25.00	RT & LT
1	1211 + 45.00	LT
1	1211 + 85.00	RT
2	1212 + 50.00	RT & LT
2	1214 + 00	RT & LT
1	1238 + 50.00	LT
1	1239 + 50.00	RT
1	1240 + 00	RT
1	1240 + 50.00	RT
1	1241 + 00	LT
1	1241 + 50.00	LT
2	1242 + 00	RT & LT
1	1243 + 00	LT
2	1357 + 00	RT & LT
2	1358 + 75.00	RT & LT
1	1359 + 00	RT
2	1359 + 50.00	RT & LT
2	1361 + 00	RT & LT
30	TOTAL	

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION
6	2 at each culvert location determined by R.E.
6	TOTAL

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS

EACH	LOCATION	
1	1211 + 65.00	
1	1359 + 17.00	
1	1214 + 00	
3	TOTAL	

70106700 TEMPORARY RUMBLE STRIP

EACH	LOCATION	
1	1191 + 16.00	1211+65
1	1196 + 16.00	1211+65
1	1201 + 16.00	1211+65
1	1219 + 61.00	1240+74
1	1222 + 13.00	1211+65
1	1224 + 61.00	1240+74
1	1221 + 3.00	1211+65
1	1226 + 3.00	1240+74
1	1231 + 3.00	1211+65
1	1251 + 34.00	1240+74
1	1256 + 34.00	1240+74
1	1261 + 34.00	1240+74
1	1338 + 84.00	1359+16
1	1343 + 84.00	1359+16
1	1348 + 84.00	1359+16
1	1370 + 21.00	1359+16
1	1375 + 21.00	1359+16
1	1380 + 21.00	1359+16
18	TOTAL	

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION	
846.3	1206 + 13.21 - 1214 + 57.31	Stage 2 4"
336.0	1209 + 94.03 - 1213 + 29.56	Stage 2 4"
639.8	1208 + 78.20 - 1215 + 15.86	Stage 3 4"
318.0	1209 + 99.03 - 1213 + 16.88	Stage 3 4"
222.0	1208 + 3.20 - 1215 + 15.86	CL 4"
24.0	1208 + 3.20	Stop Bar 12"
345.0	1239 + 61.00 - 1243 + 6	Stage 2 4"
627.0	1237 + 97.00 - 1244 + 24	Stage 2 4"
12.0	1237 + 87.00	Stop Bar 12"
12.0	1244 + 84.00	Stop Bar 12"
610.0	1238 + 63.00 - 1244 + 73	Stage 3 4"
339.0	1239 + 70.00 - 1243 + 9	Stage 3 4"
12.0	1238 + 3.00	Stop Bar 12"
12.0	1244 + 83.00	Stop Bar 12"
22.0	1240 + 20.00 - 1241 + 30	Stage 4 4"
661.0	1355 + 62.59 - 1362 + 22.81	Stage 2 4"
359.0	1357 + 32.82 - 1360 + 91.59	Stage 2 4"
777.7	1355 + 60.98 - 1363 + 36.41	Stage 3 4"
444.0	1356 + 98.68 - 1361 + 41.93	Stage 3 4"
240.0	1356 + 98.68	CL 4"
24.0	1355 + 1.00	Stop Bar 12"
6883	TOTAL	

PLOT DATE = Wed Feb 06 14:02:21 2008
 FILE NAME = C:\P\projects\2077895\807886covr.dgn
 PLOT SCALE = 600.0002 in / in
 USER NAME = harsenke