

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
17	15T-2	CARROLL	71	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION
282.1	1206 + 13.21 - 1214 + 57.31 Stage 2
112.0	1209 + 94.03 - 1213 + 29.56 Stage 2
213.3	1208 + 78.20 - 1215 + 15.86 Stage 3
106.0	1209 + 99.03 - 1213 + 16.88 Stage 3
74.0	1208 3.20 - 1215 + 15.86 CL
115.0	1208 + 3.20 - 1243 6 Stage 2
209.0	1239 61.00 - 1244 24 Stage 2
12.0	1237 97.00 Stop Bar
12.0	1244 84.00 Stop Bar
204.0	1238 63.00 Stage 3
113.0	1239 70.00 Stage 3
12.0	1238 3.00 Stop Bar
12.0	1244 83.00 Stop Bar
8.0	1240 20.00 Stage 4
220.3	1355 + 62.59 - 1362 + 22.81 Stage 2
119.7	1357 + 32.82 - 1360 + 91.59 Stage 2
259.2	1355 + 60.98 - 1363 + 36.41 Stage 3
148.0	1356 + 98.68 - 1361 + 41.93 Stage 3
80.0	1356 + 98.68 - 1361 + 41.93 Stage 3
24.0	1355 + 1.00 Stop Bar
2336	TOTAL

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
350	1209 + 90.0 - 1213 + 39 RT
374	1238 + 23.0 - 1243 + 30 RT & LT
274	1238 + 70.0 - 1242 + 84 LT
363	1357 + 35.0 - 1360 + 97 LT
1361	TOTAL

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION
275	1210 + 2 - 1212 + 77 RT
362	1239 + 55.0 - 1243 + 17 RT & LT
338	1356 + 86.0 - 1360 + 23 RT
975	TOTAL

78001100 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION
1000	1206 + 00 - 1216 + 00 RT EDGE LINE
250	1206 + 00 - 1216 + 00 CL
1000	1206 + 00 - 1216 + 00 LT EDGE LINE
936	1239 + 1.0 - 1243 + 69 RT EDGE LINE
175	1237 + 87.0 - 1244 + 84 CL
900	1355 + 00 - 1364 + 00 RT EDGE LINE
225	1355 + 00 - 1364 + 00 CL
900	1355 + 00 - 1364 + 00 LT EDGE LINE
5386	TOTAL 10772 Is two coats

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
9	1208 + 00 - 1215 + 00 CL
3	1240 + 20.00 - 1241 + 30 CL
11	1355 + 00 - 1364 + 00 CL
23	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION
25.0	1208 + 00 - 1211 + 00 CL
112.0	1209 + 94.00 - 1213 + 30 LT Edge LI
26.3	1212 + 00 - 1215 + 16 CL
112.0	1209 + 99.00 - 1213 + 35 RT Edge LI
115.0	1239 + 61.00 - 1243 + 6 RT
14.0	1237 + 87.00 - 1239 + 56 RT
20.0	1242 + 50.00 - 1244 + 84 RT
113.0	1239 + 70.00 - 1243 + 9 RT
28.2	1355 + 62.00 - 1359 + 00 CL
120.0	1357 + 32.00 - 1360 + 92 LT Edge LI
31.4	1359 + 60.00 - 1363 + 37 CL
148.0	1356 + 98.00 - 1361 + 42 RT Edge LI
865	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
9	1208 + 00 - 1215 + 00 CL
3	1240 + 20.00 - 1241 + 30 CL
11	1355 + 00 - 1364 + 00 CL
23	TOTAL

A2006514 TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER BALLED AND BURLAPPED

EACH	LOCATION
11	Landscape Engineer Will determine location
11	TOTAL

XX005298 REMOVE EXISTING TIMBER WALL

FOOT	LOCATION
105	1239 + 86.00 - 1240 + 85LT
105	TOTAL

Z0023600 FILLING EXISTING CULVERTS

EACH	LOCATION
1	1239 + 73.0
1	TOTAL

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
1	1209 + 88.0 RT
1	1213 + 42.0 RT
1	1212 + 77.0 LT NARROW
1	1239 + 56.0 RT NARROW
1	1243 + 30.0 RT
1	1242 + 84.0 LT NARROW
1	1357 + 34.0 RT
1	1360 + 99.0 RT
1	1360 + 23.0 RT NARROW
9	TOTAL

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
1	1209 + 98.0 LT
1	1239 + 55.0 LT NARROW
1	1243 + 17.0 LT
1	1356 + 85.0 LT
4	TOTAL

PLOT DATE = Mon, Jan 29 10:52:13 2008
 FILE NAME = C:\p\2007\64c35\78001100.dgn
 PLOT SCALE = 6000.0000 in / in
 USER NAME = hmsa001e