

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN
			X271-2A 80% Fed/ 20% State TOTAL QUANTITY
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	17,370
50500505	STUD SHEAR CONNECTORS	EACH	11,808
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	36
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	<del>177,290</del> 174,460
50800515	BAR SPLICERS	EACH	1,560
51100100	SLOPE WALL 4 INCH	SQ YD	654
51205200	TEMPORARY SHEET PILING	SQ FT	<del>302</del> 412
51500100	NAME PLATES	EACH	2
52000050	PREFORMED JOINT SEAL 4"	FOOT	222
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	36
52100520	ANCHOR BOLTS, 1"	EACH	72
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	129
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	7
60107600	PIPE UNDERDRAINS 4"	FOOT	3,004
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	238
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	4
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	912.50
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2
63200310	GUARDRAIL REMOVAL	FOOT	1,063
63500105	DELINEATORS	EACH	6
64200105	SHOULDER RUMBLE STRIP	FOOT	1,995
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7
67100100	MOBILIZATION	L SUM	1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	2
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6
<del>70103710</del>	<del>TRAFFIC CONTROL FOR RAMP</del>	<del>L SUM</del>	<del>1</del>
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20

\*SPECIALTY ITEMS

ADDED 4/8/08