SCHEDULE OF QUANTITIES

52000050 **PREFORMED JOINT SEAL 4'**

FOOT	LOCATION	
	I-80	
57	RT	216 + 69.18
54	LT	216 + 39.44
54	RT	219 + 24.50
57	LT	218 + 94.64
222	**TOTAL**	

60100060 **CONCRETE HEADWALL FOR PIPE DRAINS**

EACH	LOCATION			
	I-80			
1	RT	210 + 49.55	Mainline	If Needed
1	LT	214 + 07.81	Mainline	If Needed
1	LT	214 + 90.05	Mainline	If Needed
1	RT	215 + 00.00	Mainline	If Needed
1	LT	215 + 29.54	Mainline	If Needed
1	LT	220 + 44.88	Mainline	If Needed
1	LT	226 + 19.24	Mainline	If Needed
7	**TOTAL**			

60107600 **PIPE UNDERDRAINS 4"**

FOOT	LOCATION				
	I-80				
1015	RT	205 + 09.04	-	215 + 24.34	Mainline
18	RT	210 + 49.55			Mainline If Needed
224	LT	213 + 72.04	-	215 + 96.05	Mainline
35	LT	214 + 07.81			Mainline If Needed
175	RT	214 + 51.58	-	216 + 26.15	Mainline
36	LT	214 + 90.05			Mainline If Needed
32	RT	215 + 00.00			Mainline If Needed
41	LT	215 + 29.54			Mainline If Needed
159	LT	219 + 44.46	-	221 + 03.11	Mainline
232	RT	219 + 66.25	-	221 + 98.09	Mainline
35	LT	220 + 44.88			Mainline If Needed
980	LT	220 + 51.90	-	230 + 31.58	Mainline
23	LT	226 + 19.24			Mainline If Needed
3004	**TOTAL**				

63000000 **STEEL PLATE BEAM GUARDRAIL, TYPE A**

FOOT	LOCATION			
	I-80			
300.00	LT	213 + 06.38	-	216 + 06.21
125.00	RT	215 + 26.04	-	216 + 24.16
62.50	RT	215 + 88.19	-	216 + 50.59
75.00	LT	219 + 13.58	-	219 + 89.30
125.00	LT	219 + 18.62	-	220 + 41.75
225.00	RT	219 + 57.90	-	221 + 82.87
912.50	**TOTAL**			

63100045 **TRAFFIC BARRIER TERMINAL, TYPE 2**

EACH	LOCATION			
	I-80			
1	LT	212 + 93.97	-	213 + 06.38
1	RT	221 + 82.87	-	221 + 95.80
2	**TOTAL**			

⚠ NEW SHEET 4/8/08

FILE NAME = C:\Projects\p200407\d00407cvr.dgn	USER NAME = jordanhd	DESIGNED - ___	REVISED - ___	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	____ I-80 SCHEDULE OF QUANTITIES ____	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - ___	REVISED - ___			80	81-1HBY-D	ROCK ISLAND	120	18
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - ___	REVISED - ___					CONTRACT NO. 64C74		
	PLOT DATE = Wed Apr 02 07:01:45 2008	DATE - _____	REVISED - ___		SCALE: _____ SHEET NO. __ OF ___ SHEETS STA. _____ TO STA. _____	FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		