

# SCHEDULE OF QUANTITIES

**63100085 TRAFFIC BARRIER TERMINAL, TYPE 6**

EACH	LOCATION		
	I-80		
1	LT	216 + 06.21 -	216 + 51.90
1	RT	216 + 48.84 -	216 + 94.54
1	RT	216 + 50.59 -	216 + 96.29
1	LT	218 + 67.87 -	219 + 13.58
1	LT	218 + 72.92 -	219 + 18.59
1	RT	219 + 12.20 -	219 + 57.90
<b>6</b>	<b>TOTAL</b>		

**63100167 TRAFFIC BARRIER TERMINAL, TYPE I, (SPECIAL) TANGENT**

EACH	LOCATION		
	I-80		
1	RT	215 + 38.48 -	215 + 88.19
1	LT	219 + 89.30 -	220 + 38.67
<b>2</b>	<b>TOTAL</b>		

**63100169 TRAFFIC BARRIER TERMINAL, TYPE I, (SPECIAL) FLARED**

EACH	LOCATION		
	I-80		
1	RT	215 + 26.09	
1	LT	220 + 41.92	
<b>2</b>	<b>TOTAL</b>		

**63200310 GUARDRAIL REMOVAL**

FOOT	LOCATION		
	I-80		
314	LT	213 + 37.65 -	216 + 51.62
83	RT	215 + 36.36 -	216 + 19.29
152	RT	215 + 40.01 -	216 + 92.19
180	LT	218 + 68.00 -	220 + 48.15
279	RT	219 + 12.15 -	221 + 91.04
55	LT	219 + 72.88 -	220 + 27.72
<b>1063</b>	<b>TOTAL</b>		

**63500105 DELINEATORS**

EACH	LOCATION		
	I-80		
1	LT	213 + 37.65	
1	RT	215 + 36.36	
1	RT	215 + 40.01	
1	LT	218 + 68.00	
1	RT	219 + 12.15	
1	LT	219 + 72.88	
<b>6</b>	<b>TOTAL</b>		

**64200105 SHOULDER RUMBLE STRIP**

FOOT	LOCATION			
	I-80			
1015	RT	205 + 09.05 -	215 + 24.35	10' Shoulder
980	LT	220 + 51.90 -	230 + 31.58	10' Shoulder
<b>1995</b>	<b>TOTAL</b>			

**70106700 TEMPORARY RUMBLE STRIP**

EACH	LOCATION			
	IL 84			
3	LT	32 + 91.98		Stages 3 & 4 - If needed
3	RT	131 + 97.86		Stages 3 & 4 - If needed
<b>6</b>	<b>TOTAL</b>			

**70301000 WORK ZONE PAVEMENT MARKING REMOVAL**

SQ. FT.	LOCATION			
	I-80			
	Stage I			
614	RT	181 + 30.49 -	199 + 71.48	White
44	RT	199 + 91.29 -	201 + 23.82	White - Ramp
106	RT	199 + 91.29 -	203 + 09.04	White
131	LT	232 + 31.58 -	236 + 24.45	White
60	LT	234 + 43.43 -	236 + 24.45	White - Ramp
595	LT	236 + 74.26 -	254 + 57.93	White
	Stage II			
1053	RT	194 + 36.00 -	225 + 95.18	White
156	RT	211 + 57.93 -	216 + 26.14	White
32	RT	214 + 46.83 -	215 + 43.50	White - Ramp
251	RT	215 + 77.06 -	223 + 29.69	White
712	RT	216 + 26.14 -	221 + 95.23	White - Skip Dash
117	RT	221 + 95.23 -	225 + 45.65	White
20	RT	222 + 95.89 -	223 + 57.21	White - Ramp
1047	LT	209 + 90.86 -	241 + 33.00	White
94	LT	210 + 40.80 -	213 + 24.03	White
27	LT	211 + 81.85 -	212 + 61.83	White - Ramp
251	LT	212 + 44.55 -	219 + 98.58	White
776	LT	213 + 24.03 -	219 + 44.25	White - Skip Dash
362	LT	219 + 44.25 -	230 + 31.58	White
16	LT	220 + 51.82 -	220 + 99.29	White - Ramp
	Stage III			
760	RT	200 + 43.35 -	223 + 22.55	White
758	LT	212 + 53.48 -	235 + 26.56	White
	IL 84			
80	LT	32 + 72.21 -	33 + 11.74	White - 24" Stop Bar (Stage 3 and 4)
96	RT	33 + 35.75 -	33 + 83.53	White - 24" Stop Bar (Stage 3 and 4)
80	LT	131 + 14.71 -	131 + 54.28	White - 24" Stop Bar (Stage 3 and 4)
96	RT	131 + 78.34 -	132 + 25.94	White - 24" Stop Bar (Stage 3 and 4)
<b>8,333</b>	<b>TOTAL</b>			

**70400100 TEMPORARY CONCRETE BARRIER**

FOOT	LOCATION			
	I-80			
1,187.5	RT	210 + 86.81 -	222 + 70.29	STAGE II
1,162.5	LT	213 + 24.07 -	224 + 76.83	STAGE II
<b>2,350</b>	<b>TOTAL</b>			

**70400200 RELOCATE TEMPORARY CONCRETE BARRIER**

FOOT	LOCATION			
	I-80			
900	LT	214 + 60.40 -	223 + 53.52	STAGE III
912.5	RT	212 + 00.02 -	221 + 01.48	STAGE III
<b>1,812.5</b>	<b>TOTAL</b>			



REVISIED 4/8/08