

SCHEDULE OF QUANTITIES

78200520 **BARRIER WALL MARKERS, TYPE B**

EACH	LOCATION			
	I-80			
4	LT	216 + 51.91 -	218 + 67.89	Exterior Wall
4	LT	216 + 67.58 -	218 + 81.56	Interior Wall
4	RT	216 + 82.44 -	218 + 97.46	Interior Wall
4	RT	216 + 96.44 -	219 + 12.20	Exterior Wall
16	TOTAL			

78201000 **TERMINAL MARKER - DIRECT APPLIED**

EACH	LOCATION			
	I-80			
1	RT	215 + 14.05		Median
1	RT	215 + 38.48		10' Shoulder (Ramp)
1	LT	220 + 38.67		10' Shoulder (Ramp)
1	LT	220 + 53.67		Median
4	TOTAL			

78300100 **PAVEMENT MARKING REMOVAL**

SQ. FT.	LOCATION			
	I-80			
	Stage II			
377	RT	204 + 94.87 -	216 + 26.14	White - 4"
71	RT	216 + 26.14 -	221 + 91.58	White - 6" (Skip Dash)
118	RT	221 + 91.58 -	225 + 45.65	White - 4"
93		214 + 46.83 -	215 + 86.29	White - 8" (Ramp)
251	RT	215 + 77.06 -	223 + 29.69	White - 4"
66	RT	222 + 31.24 -	223 + 57.21	White - 8" (Ramp)
94	LT	210 + 40.80 -	213 + 24.03	White - 4"
78	LT	213 + 24.03 -	219 + 44.25	White - 6" (Skip Dash)
362	LT	219 + 44.25 -	230 + 30.38	White - 4"
93	LT	211 + 81.85 -	213 + 22.07	White - 8" (Ramp)
84	LT	219 + 43.88 -	220 + 99.29	White - 8" (Ramp)
251	LT	212 + 44.55 -	219 + 98.58	White - 4"
1938	TOTAL			

78300200 **RAISED REFLECTIVE PAVEMENT MARKER REMOVAL**

EACH	LOCATION			
	I-80			
3	LT	216 + 72.96 -	218 + 63.56	Between Through Lanes
3	RT	216 + 97.97 -	218 + 88.29	Between Through Lanes
6	TOTAL			

X7030100 **WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III**

FOOT	LOCATION			
	I-80			
	Stage I			
1,841	RT	181 + 30.49 -	199 + 71.48	White
133	RT	199 + 91.29 -	201 + 23.82	White - Ramp
318	RT	199 + 91.29 -	203 + 09.04	White
393	LT	232 + 31.58 -	236 + 24.45	White
181	LT	234 + 43.43 -	236 + 24.45	White - Ramp
1,784	LT	236 + 74.26 -	254 + 57.93	White
	Stage II			
3,159	RT	194 + 36.00 -	225 + 95.18	White
468	RT	211 + 57.93 -	216 + 26.14	White
97	RT	214 + 46.83 -	215 + 43.50	White - Ramp
753	RT	215 + 77.06 -	223 + 29.69	White
1,423	RT	216 + 26.14 -	221 + 95.23	White - Skip Dash
350	RT	221 + 95.23 -	225 + 45.65	White
61	RT	222 + 95.89 -	223 + 57.21	White - Ramp
3,142	LT	209 + 90.86 -	241 + 33.00	White
283	LT	210 + 40.80 -	213 + 24.03	White
80	LT	211 + 81.85 -	212 + 61.83	White - Ramp
754	LT	212 + 44.55 -	219 + 98.58	White
1,551	LT	213 + 24.03 -	219 + 44.25	White - Skip Dash
1,086	LT	219 + 44.25 -	230 + 31.58	White
47	LT	220 + 51.82 -	220 + 99.29	White - Ramp
	Stage III			
2279	RT	200 + 43.35 -	223 + 22.55	White
2273	LT	212 + 53.48 -	235 + 26.56	White
	IL 84			
40	LT	32 + 72.21 -	33 + 11.74	White - 24" Stop Bar (Stage 3 and 4)
48	RT	33 + 35.75 -	33 + 83.53	White - 24" Stop Bar (Stage 3 and 4)
40	LT	131 + 14.71 -	131 + 54.28	White - 24" Stop Bar (Stage 3 and 4)
48	RT	131 + 78.34 -	132 + 25.94	White - 24" Stop Bar (Stage 3 and 4)
22,631	TOTAL			

Z0001050 **AGGREGATE SUBGRADE 12"**

SQ. YD	LOCATION			
	I-80			
246	LT	215 + 96.16 -	216 + 39.44	CRC Pavement
265	RT	216 + 26.11 -	216 + 69.18	CRC Pavement
304	LT	218 + 94.64 -	219 + 43.38	CRC Pavement
244	RT	219 + 22.97 -	219 + 66.32	CRC Pavement
1,060	TOTAL			

Z0030250 **IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3**

EACH	LOCATION			
	I-80			
1	RT	210 + 86.81		STAGE II
1	RT	212 + 00.02		STAGE III
1	LT	223 + 53.52		STAGE III
1	LT	224 + 76.84		STAGE II
4	TOTAL			

▲ NEW SHEET 4/8/08

FILE NAME =	USER NAME = jordanhd	DESIGNED -	REVISED -	STATE OF ILLINOIS	I-80 SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\Projects\p200407\00407crr.dgn		DRAWN -	REVISED -	DEPARTMENT OF TRANSPORTATION		80	BI-JHBY-D	ROCK ISLAND	120	21
		PLOT SCALE = 50.0000' / IN.	CHECKED -							CONTRACT NO. 64C74
		PLOT DATE = Wed Apr 02 07:02:22 2008	DATE -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____	TO STA. _____	FED. ROAD DIST. NO. _____	ILLINOIS FED. AID PROJECT