

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN X271-2A 80% Fed/ 20% State TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	1,123
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	233
25000210	SEEDING, CLASS 2A	ACRE	1.75
25100630	EROSION CONTROL BLANKET	SQ YD	8,228
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,020
25000750	MOWING	ACRE	1.75
28000400	PERIMETER EROSION BARRIER	FOOT	2,745
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	3,875
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	1,060
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.4
40600300	AGGREGATE (PRIME COAT)	TON	14
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	355
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,344
40600990	TEMPORARY RAMP	SQ YD	401
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	1,143
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	740
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,060
44000700	APPROACH SLAB REMOVAL	SQ YD	740
44002100	CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL	SQ YD	816
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,379
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	3,379
50102400	CONCRETE REMOVAL	CU YD	62
50104650	SLOPE WALL REMOVAL	SQ YD	676
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2
50157300	PROTECTIVE SHIELD	SQ YD	1,455
50200100	STRUCTURE EXCAVATION	CU YD	233
50300225	CONCRETE STRUCTURES	CU YD	2.60
50300255	CONCRETE SUPERSTRUCTURES	CU YD	726.9
50300260	BRIDGE DECK GROOVING	SQ YD	2,208
50300300	PROTECTIVE COAT	SQ YD	2,659

*SPECIALTY ITEMS
▲ NP 100% STATE